

1080235

TO: STATE CORPORATION COMMISSION

12-17

API NUMBER 15-101-21,391-00-0 27  
SW SW NE SEC. 21, T 17 S, R 24 W

CONSERVATION DIVISION - PLUGGING SECTION \_\_\_\_\_ FEET FROM SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET \_\_\_\_\_ FEET FROM SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME RUSSELL WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY LANE 151.09

OPERATOR LICENSE # 31627 WELL TOTAL DEPTH 4649 FEET

OPERATOR: WHITETAIL CRUDE, INC PRODUCTION CSG: SIZE 4 1/2" @ 4649' WITH 200 SX

NAME AND PO BOX 544 SURFACE CASING: SIZE 8 5/8" @ 302' WITH 165 SX

ADDRESS NESS CITY, KS 67560

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ INJ WELL \_\_\_\_\_ D/A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR ALLIED CEMENTING CO, INC LICENSE NUMBER NA

ADDRESS PO BOX 31, RUSSELL, KS 67665

COMPANY TO PLUG AT: HOUR: 1:30 PM DAY: 17 MONTH: 12 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM \_\_\_\_\_

(COMPANY NAME) ALLIED CEMENTING CO INC (PHONE) 785-483-3887

WERE: PERFS AT 4216-19, 4185-88, 4144-47 DV TOOL @ 2087' W/400 SX CEMENT. CMT TO SURFACE ALLIED PUMPED DOWN 4 1/2" CASING 300# HULLS AND 25 SX CEMENT WITH 50# HULLS MIXED IN, 11 SX GEL, 170 SX CEMENT. MAXIMUM PSI PRESSURE 800#, SHUT IN AT 400#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULAS 10 SX CEMENT PRESSURED UP TO 500# SHUT IN.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 2:30 PM DAY: 17 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT \_\_\_\_\_

ALLIED PUMPED DOWN 4 1/2" CASING 300# AND 25 SX CEMENT WITH 50# HULLS MIXED IN 11 SX GEL, 170 SX CEMENT. MAXIMUM PSI 800# SHUT IN AT 400#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULAS 10 SX CEMENT PRESSURED UP TO 500# SHUT IN.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)  
I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin D. Strube (TECHNICIAN) FORM CP 2/3

RECEIVED BY  
Wichita Kansas  
JAN - 4  
01-04-98

JAN 06 1999

60513