

3-18-88

1 061077

API NUMBER 15- 101-21,461-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C N/2 NW SE, SEC. 21, T 17 S, R 27 W/EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2310 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Lease Name Hanks "E" Well # 2

Operator: Mull Drilling Company, Inc.

County Lane 150.31

Name & Address P.O. Box 2758

Well Total Depth 4625 feet

Wichita, KS 67201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 370

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 8 p.m. Day: 18 Month: 3 Year: 19 88

Plugging proposal received from Tony Martin

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2660' GL Anhydrite 2078-2108'

1st plug at 2100' with 50 sx cement, 2nd plug at 1350' with 80 sx cement,

3rd plug at 400' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:15 p.m. Day: 18 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement,

2nd plug at 1350' with 80 sx cement,

3rd plug at 400' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAR 23 1988

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. (If additional description is necessary, use BACK of this form.)

INVOICED (observe this plugging.)

DATE 3-25-88

Signed Paul A. Luthi (TECHNICIAN)

NOV. NO. 20203

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... March 15, 1988

API Number 15-101-21,461-00-00

OPERATOR: License # 5144
Name Mull Drilling Company, Inc.
Address P.O. Box 2758
City State/Zip Wichita, KS 67201
Contact Person Paul Gunzelman
Phone (316) 264-6366

CN/2 NW SE Sec 21 Twp 17 S Rg 27
2310
1980

CONTRACTOR: License # 5422
Name Abercrombie Drilling, Inc.
City/State 801 Union Center, Wichita, KS 67202

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 330 feet
County Lane
Lease Name Hanks 'E' Well # 2
Ground surface elevation GL 2676' feet MSI
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water 180'
Depth to bottom of usable water 1250'
Surface pipe by Alternate: 1 2 X
Surface pipe planned to be set 350'±
Conductor pipe required
Projected Total Depth 4675' feet
Formation Mississippian

Well Drilled For: Well Class: Type Equipment:
X Oil Storage X Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expi Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 3/7/88 Signature of Operator or Agent Paul M. Gunzelman Title Geologist/Kansas Div.

For KCC Use:
Conductor Pipe Required 9-8-88 feet; Minimum Surface Pipe Required 200 feet per Alt. X 2
This Authorization Expires 9-8-88 Approved By 3-8-88

EFFECTIVE DATE: 3-13-88
Get 350+ of 8 5/8 on 3-11-88

CN/2 NW SE Sec 21 Twp 17 S Rg 27 XX West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays). (Per Steve Pfeiffer)

Table with 3 columns: Plug depth (ft), Formation, and Sacks. Includes entries for 1st plug (2776' ft, 50 sacks), 2nd plug (1340' ft, 80 sacks), 3rd plug (350' ft, 40 sacks), 4th plug (40' ft, 10 sacks), 5th plug (Rathole, 15 sacks), and Mousehole (10 sacks).

Vertical list of well parameters:
PUSHER Tony Martin
TD 4625' FORMATION Miss
SURFACE PIPE 8 5/8 @ 370'
ANHYDRITE 2078 ELEVATION 2660 8/8
STARTING TIME & DATE 8:00 p 7-18-88
COMPLETION TIME & DATE 10:15 p 3-18-88
1st PLUG @ 2100 FT. W/ 50 SX
2nd PLUG @ 1350 FT. W/ 80 SX
3rd PLUG @ 400 FT. W/ 50 SX
4th PLUG @ 400 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Allied
TECHNICIAN PAL
60/40 w/ 6% gel

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1988
CONSERVATION DIVISION
Wichita, Kansas