

070872

10-30

To: 1
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

API NUMBER 15-101-20,281-00-00

SE NW NW, SEC. 16, T 17 S, R 27 W/E
4290 feet from S section line

4290 feet from E section line

Lease Name Selfridge "B" Well # 1

County Lane 151.45

Well Total Depth 4660 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 246

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Operator: Mull Drilling Company, Inc.

Name:

Address P.O. Box 2758

Wichita, KS 67201

Abandoned Oil Well X Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:45 a.m. Day: 30 Month: 10 Year: 19 90

Plugging proposal received from

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4659' w/100 sx cement, PBTD 4340', Perfs at 4262-4303'

1st plug sand back to 4210' and dump 5 sx cement on top of sand through bailer,

2nd plug shoot at 1200', pump 80 sx cement,

3rd plug pump 80 sx cement at 850', 4th plug pump 50 sx cement at 275',

5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Case Morris D.G.
 (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 2:45 p.m. Day: 30 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4210' and dumped 5 sx cement on top of

sand through bailer,

2nd plug shot at 2400', 2000', 1600', and 1200'. Pumped 70 sx cement down 5 1/2", displaced
to 1000',

3rd plug shot casing at 842', pulled to 620' and spotted 40 sx cement,

4th plug pulled to 260' and spotted 40 sx cement, 5th plug topped off with 20 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 840' of 5 1/2" casing.
 (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-6-90INV. NO. 29834

10-30

NOV 1 1990
 CONSERVATION DIVISION
 Wichita, Kansas

Signed

(TECHNICIAN)

FORM CP-2/3
 Rev. 01-84