

7-22-88

To: 1 070566
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101 - 20,288-00-00

NE, NW, NE, SEC. 16, T 17 S, R 27 W/E

4950 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Lease Name Selfridge "A" Well # 2

Operator: Mull Drlg.

County Ness 150.96

Name & Address Box 2758

Well Total Depth 4645' feet

Wichita, Ks. 67201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8-5/8" feet 244

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Ks. 67524

Company to plug at: Hour: 4:45 PM Day: 22 Month: 7 Year: 19 88

Plugging proposal received from Dallas Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

work: Bottom Plug, sand to 4200', 5SX, cement 5 1/2" @ 4643', Perfs 4245'-4588'

1st plug pump down 5 1/2", 200 SX, 60/40 poz. 67% gel

2nd plug pump down 5 1/2" X 8 5/8" annulus, 100 SX, 60/40 poz. 67% gel

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:20 M Day: 22 Month: 7 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2", 200 SX, 60/40 poz. 67% gel

2nd plug pumped down annulus, 100 SX, 60/40 poz. 67% gel

Max. pressure on 5 1/2" 500#, shut in 100 #

Max. pressure on annulus 200#, shut in 100 #

RECEIVED STATE CORPORATION COMMISSION

JUL 28 1988

Remarks: No casing recovery, shot off pipe @ 1200' (If additional description is necessary, use BACK of this form.)
Wichita, Kansas Allied Cementers

INVOICED observe this plugging.

DATE 8-8-88

Signed Dan Luthi (TECHNICIAN)

INV. NO. 21755