

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20876-00-00
Spot: CSWNWNW Sec/Twnshp/Rge: 15-17S-27W
990 feet from N Section Line, 330 feet from W Section Line
Lease/Unit Name: E JOE Well Number: 1
County: LANE Total Vertical Depth: 4660 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: PO BOX 2758 221 N MAIN STE 300
WICHITA, KS 67201

Conductor Pipe: Size feet: 8 1/2
Surface Casing: Size 8.625 feet: 312 WITH 240 SX CMT
Production: Size 4.5 feet: 4658 WITH 175 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/15/2002 9:15 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: BILLY STUM Company: MULL DRILLING Phone: (316) 264-6366

Proposed Plugging Method: SET CIBP @ 4125' & 2 SX CMT ON TOP WITH BAILER OR RUN TUBING TO BOTTOM AND PUMP 200# HULLS WITH 20 SX CMT. RUN TUBING TO 2100' & CIRCULATE CMT TO SURFACE. PULL TUBING AND TOP OFF 4 1/2" WITH CMT. TIE ON TO ANNULUS AND SQUEEZE WITH 100 SX CMT IF POSSIBLE.

Plugging Proposal Received By: SCOTT ALBERG
Date/Time Plugging Completed: 01/15/2002 1:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4125'. PERFS AT 4183-88'. PERFORATED AT 1849' WITH 275 SX CMT, 1050' WITH 50 SX CMT. 100 SX CMT DOWN BACKSIDE. CIBP @ 4125' WITH 2 SX CMT. RUN TUBING TO 2096' & PUMP 112 SX CMT AND HULLS. DID NOT CIRCULATE. PULLED TUBING. WAITED 2 1/2 HOURS AND TAGGED CMT AT 400'. PUMPED 28 SX CMT & 200# HULLS. CMT CIRCULATED. TIED ON TO BACKSIDE AND PRESSURED TO 600# AND HELD. 01/16/02: CMT FELL 250'. TOPPED OFF WITH 15 SX CMT. STAYED FULL.

RECEIVED
FEB - 4 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED-2 STAGED.

Plugged through: TBG

District: 01

Signed

Michael Maier
(TECHNICIAN)

INVOICED JAN 17 2002

DATE Feb 6-02

WV. NO. 2002061339

Form 23