

To: 1650043
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-101-21,205 -00-00
SE NW SW, SEC. 15, T. 17 S, R. 27 W/E
1650 feet from S section line
4290 feet from E section line

6-14
TECHNICIAN'S PLUGGING REPORT

Operator License # 4629
Operator: Brito Oil Company, Inc.
Name:
Address 120 S. Market, Ste. 300
Wichita, KS 67202

Lease Name Massey Well # 1
County Lane
Well Total Depth 4660.151.45 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 219

Abandoned Oil Well Gas Well Input Well SMD Well O&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 11:15 a.m. Day: 14 Month: 6 Year: 19 96

Plugging proposal received from Richard

(company name) Mike's Testing & Salvage (phone) 316-938-2943

were: 4 1/2" at 4658' w/250 sx cement, PBD 4658', Perfs at 3583-88, 4192-96, 4231-35, 4590-95'

Two-staged. Apparently CIBP set at approx. 4100'. Approx. 1800' of cement from surface.

1st plug pump 2 sx hulls, 25 sx cement, 10 sx gel, and 105 sx cement.

Check backside.

Plugging Proposal Received by Kevin Strube
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12 p.m. Day: 14 Month: 6 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls, 25 sx cement, 11 sx gel, and 105
sx cement. Maximum pressure 1000 psi.

Shut in 4 1/2" at 800 psi.

2nd plug went down 8 5/8" X 4 1/2" and pumped 15 sx cement.

Maximum pressure 400 psi. Shut in.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE JUN 24 1996
45853
observe this plugging.

Signed Kevin D. Strube
(TECHNICIAN)