

To: 1 130044  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 101-20,514 -00-00  
SW NE SW, SEC. 15, T 17 S, R 27 W/E  
1650 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT 6-17  
Operator License # 4629  
Operator: Brito Oil Company, Inc.  
Name & Address: 120 S. Market, Ste. 300  
Wichita, KS 67202

Lease Name Massey Well # 2  
County Lane  
Well Total Depth 4777 155.25 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 513

Abandoned Oil Well  Gas Well  Input Well  SMO Well  D&A   
Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage License Number 31529  
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 1:15 p.m. Day: 14 Month: 6 Year: 19 96

Plugging proposal received from Richard McIntyre  
(company name) Mike's Testing & Salvage (phone) 316-938-2943

logs: 4 1/2" at 4775', PBD 4775', Perfs at 4291-93'  
1st plug sand back to 4250' and dump 4 sx cement on top of sand through bailer,  
2nd plug at 2100' with 50 sx cement,  
3rd plug at 1200' with 80 sx cement,  
4th plug at 530' with 50 sx cement.

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 18 1996

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)  
WICHITA, KS  
CONSERVATION DIVISION

Plugging Operations attended by Agent?: All  Part  None   
Operations Completed: Hour: 11:15 a.m. Day: 17 Month: 6 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 4140' and dumped 4 sx cement on top of sand through bailer,

2nd plug shot casing at 1200' and ran 2 3/8" tubing to 1200'. Pumped 90 sx cement, pulled tubing.  
3rd plug shot 4 1/2" casing at 500' and pumped 190 sx cement down 4 1/2" casing.  
Well on vacuum. Cement down 480' by 3 p.m.

4th plug 6/17/96 Witnessed by Richard Lacey. Cement top at 428'. Shot pipe at 419' and circulated 110 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
DATE JUN 24 1996  
4585K

Signed Kevin P. Shultz  
(TECHNICIAN)