

1 090325

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,602 - 00 - 00

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Operator: Mull Drilling Company, Inc.  
Name & Address: P. O. Box 2758  
Wichita, KS 67201

150' N N/2 SW, SEC. 16, T 17 S, R 27 W/EX  
750 feet from S section line  
4620 feet from E section line

Lease Name Eitel Well # 1

County Lane 149.83

Well Total Depth 4610 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 283 ✓

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:10 am Day: 24 Month: April Year: 19 85

Plugging proposal received from Ron Hoover

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4610' PBTD 4301' Perfs at 4247-52'

1st plug sand back to 4190' and dump 4sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Robert B. Tarbutton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 am Day: 24 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4190' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAY 02 1985

Maximum pressure 1400 psi and shut in 300 psi

CONSERVATION DIVISION

Remarks: Recovered 1730' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

I (did / ~~xxxxxx~~) observe this plugging.

Signed Robert B. Tarbutton (TECHNICIAN)

5-7-85  
8019