

1 060514

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW SW SE , SEC. 16 , T 17 S, R 27 W/R
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,127-00-00

330 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Lease Name Eitel 'C' Well # 1

Operator: Mull Drilling Company, Inc.

County Lane 148.82

Name & Address P. O. Box 2758

Well Total Depth 4579 feet

Wichita, KS 67201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 387

Abandoned Oil Well Gas Well Input Well SWD Well O&AX

Other well as hereinafter indicated

Plugging Contractor D N B Drilling, Inc. License Number 5476

Address 535 North Oliver, Wichita, KS 67208

Company to plug at: Hour: 10:30 pm Day: 15 Month: March Year: 19 85

Plugging proposal received from John Taylor

(company name) D N B (phone) 316-687-5471

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2060' with 50 sx cement

2nd plug at 1280' with 50 sx cement

3rd plug at 430' with 50 sx cement
solid bridge

4th plug hulls - plug at 40'-- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement
Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

X

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: midnight Day: 15 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2060' with 50 sx cement, 2nd plug at 1280' with 50

sx cement, 3rd plug at 430' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 25 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(if additional description is necessary, use BACK of this form.)

(check / did not) observe this plugging.

DATE 3-26-85

Signed Paul A. Luthi
(TECHNICIAN)

I.V. NO. 7446