

1 061040

12-7-87

API NUMBER 15-101-21,435-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION N/2 S/2 SW, SEC. 16, T 17 S, R 27 W/8
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

990 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Lease Name Eitel "B" Well # 1-16

Operator: Landmark Oil Exploration, Inc.
Name & Address: 110 South Main, Suite 510
Wichita, KS 67202

County Lane 151.13
Well Total Depth 4650 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 271

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Beredco Inc. License Number 5147

Address 401 East Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 1:45 p.m. Day: 7 Month: 12 Year: 19 87

Plugging proposal received from Howard Cain

(company name) Beredco Inc. (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2686' KB
Anhydrite 2090-2121'

1st plug at 2120' with 50 sx cement, 2nd plug at 1360' with 80 sx cement,
3rd plug at 300' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 7 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2120' with 50 sx cement,
2nd plug at 1360' with 80 sx cement,
3rd plug at 300' with 40 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE 12-9-87

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 19242

12-7

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date November 18, 1987

API Number 15-101-21,435-00-00

OPERATOR: License # 06113
Name Landmark Oil Exploration, Inc.
Address 110 S. Main, Suite 510
City/State/Zip Wichita, KS
Contact Person Jeff Wood
Phone 316/265-8181

N/2 S/2 SW Sec 16 Twp 17 S, Rg 27
990 Ft. from South Line of Section
3960 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5147
Name Beredco Inc
City/State Wichita, KS

Nearest lease or unit boundary line 990 feet
County Lane

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Est Air Rotary
OWWO X Expl X Wildcat Cable

Lease Name Eitel "B" Well # 1-16
Ground surface elevation unknown feet MSL
Domestic well within 330 feet yes X no
Municipal well within one mile yes X no

If OWWO: old well info as follows:

Depth to bottom of fresh water 100
Depth to bottom of usable water 1300
Surface pipe by Alternate 1 X
Surface pipe planned to be set 250
Conductor pipe required no
Projected Total Depth 4600 feet
Formation Mississippi

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 11-9-87 Signature of Operator or Agent Title

For KCC Use:
Conductor Pipe Required 5-12-88 feet; Minimum Surface Pipe Required 200 feet per Alt. X 2
This Authorization Expires 5-12-88 Approved By FH 11-12-87

EFFECTIVE DATE: 11-17-87

N/2 S/2 SW Sec 16 Twp 17 S, Rg 27 X East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ Base Anhydrite feet depth with 50 sxs of 60-40 poz mix, 6% CaCl, 3% gel
2nd plug @ Base Cheyenne feet depth with 80 sxs of
3rd plug @ .30' Below Surface feet depth with 40 sxs of
4th plug @ .40' To Surface feet depth with 10 sxs of
5th plug @ feet depth with sxs of
(2) Rathole with 0 sxs (b) Mousehole with 10 sxs

PUSHER Howard Cane
TD 4650 FORMATION MISS
SURFACE PIPE 5 5/8 @ 271
ANHYDRITE 2121 ELEVATION 2686 K5
STARTING TIME & DATE 12-7-87 1:45 PM
COMPLETION TIME & DATE 4:00 PM
1st PLUG @ 2120 FT. WI 50 SX
2nd PLUG @ 1360 FT. WI 80 SX
3rd PLUG @ 300 FT. WI 40 SX
4th PLUG @ 40-0 FT. WI 10 SX
RAT HOLE CIRCULATED WI 15 SX
MOUSE HOLE CIRCULATED WI 10 SX
WATER WELL PLUGGED WI 10 SX
CEMENT COMPANY B.G. Eaton
TECHNICIAN Paul Luthi
60/40 w/ 6%
STATE CO. DEC 9 1987