

To: 1031314
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-31
API NUMBER 15-101-21,611 -00-00 240
NW NW SW, SEC. 19, T. 17 S, R. 27 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 4058
Operator: American Warrior, Inc.
Name & Address P.O. Box 399
Garden City, KS 67846

2310 feet from S section line
330 feet from E section line
Lease Name Collins Well # 1
County Lane 138.87
Well Total Depth 4273 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 370

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418
Address P.O. Box 1389, Great Bend, KS 67530-1389

Company to plug at: Hour: 5 p.m. Day: 31 Month: 12 Year: 19 91

Plugging proposal received from Mike
(company name) Allen Drilling Company (phone) 316-793-5681

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2116-2155'
1st plug at 2160' with 50 sx cement, 2nd plug at 1260' with 80 sx cement,
3rd plug at 410' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 9:45 p.m. Day: 31 Month: 12 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2160' with 50 sx cement,
2nd plug at 1230' with 80 sx cement,
3rd plug at 410' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 7 1991
CC. CONSERVATION DIVISION
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Halliburton.

INVOICED (additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE: 1-9-92
INV. NO. 34271

Signed Richard W. York
(TECHNICIAN)

EFFECTIVE DATE: 12-14-91

State of Kansas 15

101-21,611 - 0000

FORM MUST BE TYPED

DISTRICT # 1

NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED

SEA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

ALL BLANKS MUST BE FILLED

Expected Spud Date DECEMBER 15 1991

Spot NW SW Sec 19 Twp 17 S, Rg 27 East

OPERATOR: License # 4058 AMERICAN WARRIOR, INC. P.O. BOX 399 GARDEN CITY, KS 67846 MICHAEL J. WREATH (316) 275-2963

2310 feet from South North line of Section 330 feet from East West line of Section

IS SECTION X REGULAR IRREGULAR (NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License # 5418 ALLEN DRILLING

County: LANE Lease Name: COLLINS Well #: 1 Field Name: WHITE ROCK

Is this a Prorated/Spaced Field? yes X no

Target Formation(s): CHEROKEE

Nearest lease or unit boundary: 330

Ground Surface Elevation: 2725 EST. feet MSL

Water well within one-quarter mile: yes X no

Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 150

Depth to bottom of usable water: 1175

Surface Pipe by Alternate: 1 X 2

Length of Surface Pipe Planned to be set: 350

Length of Conductor pipe required: NONE

Projected Total Depth: 4600

Formation at Total Depth: MISSISSIPPIAN

Water Source for Drilling Operations: well X farm pond other

DVR Permit #:

Will Cores Be Taken?: yes X no

If yes, proposed zone:

Well Drilled For: Well Class: Type Equipment: X Oil Enh Rec Infield X Mud Rotary Gas Storage X Pool Ext. Air Rotary OWWO Disposal Wildcat Cable Seismic: # of Holes Other If OWWO: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth: Bottom Hole Location:

200' Alt. II Req.

AFFIDAVIT

Exp. 6/9/92

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following minimum requirements will be set:

Pusher Mike SPUD DATE 12-22-91 INIT. SA LENGTH SURFACE PLANNED RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 2 1/2 @ 370 CONDUCTOR ANHYDRITE T- B- ELEVATION TD 4370 FORMATION KCC RAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX 1 Anhydrite Base @ 2160 Ft. W/ 50 SX 2 1/2 Base Anyh. @ 1775 Ft. W/ 80 SX 1/2, 1/2 Plug @ Ft. W/ SX Bottom Surface @ 410 Ft. W/ 50 SX 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 12 SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN SA DATE 1 TYPE OF CEMENT Con. 6 To 7.650 STARTING TIME 5:00 (AM/PM) DATE 12-23-91 COMPLETION TIME 9:45 (AM/PM) DATE 2-3-91 CEMENT COMPANY Halliburton