

To: 1071039 4-t  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-20,060-00-00 8/p  
NW SW SW, SEC. 18, T. 17 S, R. 27 W/E  
990 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4058  
Operator: American Warrior, Inc.  
Name & Address: P.O. Box 399  
Garden City, KS 67846

Lease Name Collins Well # 1  
County Lane  
Well Total Depth 4638 150.73 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 366

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor American Warrior, Inc. License Number 4058  
Address P.O. Box 399, Garden City, KS 67846

Company to plug at: Hour: 10:05 a.m. Day: 1 Month: 4 Year: 19 92

Plugging proposal received from Dean Ives  
(company name) American Warrior, Inc. (phone) 913-625-7773

work: 4 1/2" at 4615' w/200 sx cement, PBTD 4566', Perfs at 4200-4552', 2-staged  
1st plug pump 750 lbs. hulls and 210 sx cement down 4 1/2".  
2nd plug pump 25 sx cement down 8 5/8".

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:45 a.m. Day: 1 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 750 lbs. hulls and 210 sx cement down 4 1/2".

Maximum pressure 1200 psi and shut in 0 psi.

2nd plug pumped 25 sx cement down 8 5/8" to 700#.

Remarks: Used 60/40 Pozmix 8% gel by Halliburton. No casing recovery.  
(if additional description is necessary, use BACK of this form.)

(did not) observe this plugging.

INVOICED  
DATE MAY 04 1992  
NO. 35105  
4-1

Signed Dan Goodrow  
(TECHNICIAN)

STATE CORPORATION COMMISSION  
RECEIVED  
MAY 10 1992  
CONSERVATION DIVISION  
WICHITA, KANSAS