

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-101-20,710 -0000 (of this well) 6/87
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Blue Goose Drilling Company, Inc. OPERATORS LICENSE NO. 5104

ADDRESS P.O. Box 1413, Great Bend, KS 67530 PHONE # (316) 792-5633

LEASE (FARM) Hagans WELL NO. 1 WELL LOCATION C NW SE COUNTY Lane

SEC. 11 TWP. 17 RGE. 27W or (W) TOTAL DEPTH 4550' PLUG BACK TO 4219'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 369' CEMENTED WITH 200 SACKS

CASING SIZE 4 1/2" SET AT 4258' CEMENTED WITH 115 SACKS

PERFORATED AT 4195-4198' & 4190-4192' & 4056-4060'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Dump sand in 4 1/2" to 50' above perms. and
2 sx cement, then pull casing. Pump 3 sx hulls, then 15 sx gel, then 50 sx cement, then 10 sx
gel, then 1 sx hulls, then 150 sx cement (60/40 pos, 6% gel). As recommended by District #1.
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Filed with ACOIS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN To be coordinated with District #1 office.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Martin E. Miller PHONE # (316) 792-5633

ADDRESS P.O. Box 1413, Great Bend, KS 67530

PLUGGING CONTRACTOR Unknown LICENSE NO. A11C 1 0 1986

ADDRESS _____ PHONE # () _____

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]
(Operator or Agent)

DATE: 8/18/84

①



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1288

THIS NOTICE

NOV 19 '86

EXPIRES

August 19, 1986

WELL PLUGGING NOTICE

Hagens #1
C NW SE
Sec. 11-17S-27W
Lane County

Blue Goose Drilling Company, Inc.
P. O. Box 1413
Great Bend, KS 67530

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Jack McCord, Director

Please contact the district office to review your suggested method of plugging

DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760

five days prior to plugging the well (KAR-82-3-113).