



15-101-20615-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Executive Secretary
STATE CORPORATION COMMISSION

State Corporation Commission

CONSERVATION DIVISION
(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

26 February 1982

MAR 2 1982
03-02-82

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Leroy Barron of Blue Goose Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Mull Drilling Co.

Complete Address: P.O. Box 2758 Wichita Kansas 67201

Lease Name: James Well No. G 1

Location: N/2 SW-SW/4 Sec. 31 Twp. 16 Rge. 28 (E) (W)

County: Lane Total Depth: 459.3'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Barron was instructed to plug the well as follows:

There is 336' of 8 1/8" surface casing cement circulated, the anhydrite was topped at 2193'. 1st plug at 2000' with 50 lbs of cement 2nd plug 900' with 35 lbs of cement. 3rd plug push rubber plug to 320' and pumped 35 lbs of cement on top of it. 4th plug 40' to 0' with 10 lbs of cement. Then circulated 10 lbs of cement in rat hole. The cement pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by Halliburton Co.

Paul Luthin
Conservation Division Agent