



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Building
WICHITA, KANSAS 67202

7-19-82

RECEIVED
JUL 28 1982
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-101-20,685-00-00

Dear Sir:

Mr. Dennis Sporing of Abercrombie Drilling Co. this date requested permission to plug the following described well:

Operator's Full Name: K. & E. Petroleum Co.

Complete Address: 100 South Main, Suite 300, Wichita, Kansas 67202

Lease Name: Lillatson Well No. 1

Location: 380' FNL - 2010' FEL Sec. 30 Twp. 16 Rge. 28 (E) (NW)

County: Lane Total Depth: 4580'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Sporing was instructed to plug the well as follows:

They set 319' of 8 5/8" surface casing. The anhydrite was topped at 2172' was from 770' to 1280'. 1st plug at 2100' with 35 bbl of cement. 2nd plug at 1700' with 150 bbl of cement. 3rd plug at 380' with 35 bbl of cement. 4th plug 40' to 0' on solid bridge with 10 bbl of cement. Then circulated 10 bbl of cement in rat hole. The cement was pumped through drill pipe with (over)

Very truly yours, (over)

Paul A. Little
Conservation Division Agent

hole full of heavy mud. The plugging was accomplished
by sun cementing.

Paul A. Little