



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 31 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bob Boyd of Helmerich & Payne, Inc. has this date requested permission to plug the following described well:

Mr. Boyd guarantees payment of the plugging fee.

Operator's full Name: Helmerich & Payne, Incorporated,

Complete Address: Box #558, Garden City, Kansas.

Lease Name: Hartzog Well No. 1

Location: CNW-<sup>SE</sup>SW Sec. 25 Twp. 16 Rge. (E)(W) 28

County Lane Total Depth 4635 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Boyd was instructed to plug the well as follows:

285'--8 5/8" Surface pipe, cement circulated with 200 Sx.  
4598'--5 1/2" Production casing cemented with 125 Sx. Top of  
cement (Temp. Survey) @ 3975. Well plugged back to 4567'.  
Top perforations from 4356' to 4360'.

Sand well back to 4340' and set 5 Sx. cement with dump bailer.  
Pull 5 1/2" to 660' and circulate heavy gel mud. Pull 5 1/2" to  
600' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 280'  
and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2", set rock bridge  
@ 35' and 10 Sx. cement to cellar.

*N. L. Dushala*  
Conservation Division Agent