

15-101-00053-00-00

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY O. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

8-10-66 AUG 10 1966

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bob Boyd of Helmerich & Payne, Inc. has this date requested permission to plug the following described well:

Mr. Bob Boyd guarantees payment of the plugging fee.

Operator's full Name: Helmerich & Payne, Incorporated,

Complete Address: Box # 558, Garden City, Kansas.

Lease Name: DeMand Well No. 1

Location: CSW-NE Sec. 25 Twp. 16 Rge. (E)(W) 28

County Lane Total Depth 4748 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Boyd was instructed to plug the well as follows:

286'--8 5/8" Surface pipe, cement circulated with 200 Sx.  
4635'--5 1/2" Production casing cemented with 175 Sx. DV tool @  
1020' with 225 Sx. cement to surface. Top perforations @ 4406'.  
Sand well back to 4375 and set 5 Sx. cement. Push plug to 300',  
set 15' rock bridge and fill to bottom of cellar. with cement.

Very truly yours,

W. L. Nichols  
Conservation Division Agent