

State of Kansas



15-101-20101-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217RECEIVED
STATE CORPORATION COMMISSION

APR 22 1974

CONSERVATION DIVISION
Wichita, KansasVERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wilmer Dreiling of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Dreiling guarantees payment of the plugging fee.

Operator's full Name: O. A. Sutton,

Complete Address: 800 Sutton Place, Wichita, Kansas.

Lease Name: Templin Well No. 2

Location: SW-SW Sec. 24 Twp. 16 Rge. (E)(W) 28

County: Lane Total Depth 4670' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dreiling was instructed to plug the well as follows:

318'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 775'.

Circulate hole with heavy mud. Pull DP to 1000' and displace 110 Cu. Ft. cement thru DP. Pull DP to 340' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent