



15-101-20045-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 4 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
2-4-74

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Incorporated,

Complete Address: 7701 E. Kellogg, Wichita, Kansas.

Lease Name: Tillston Well No. C-1

Location: NW-SE-NW Sec. 20 Twp. 16 Rge. (E)(W) 28

County: Lane Total Depth 4607' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Wasinger was instructed to plug the well as follows:

265'--8 5/8" Surface casing, cement circulated.  
4246'--5 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to 4211'. Pipe collapsed @ 2800'. Rotary mud standing in 5 1/2" @ 1200'.

Shoot and pull 5 1/2" casing and squeeze well with 5 sacks hulls, 20 sacks gel and 100 Sx. cement, staged.

Very truly yours,

H. L. Nichols  
Conservation Division Agent