

State of Kansas



15-135-20006-0050

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

1-30-67
RECEIVED
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. C. Ray Rice of Sterling Drlg. Co. Inc. has this
date requested permission to plug the following described well:

Mr. Rice guarantees payment of the plugging fee.

Operator's full Name: Sterling Drilling Company

Complete Address: Box 129 Sterling Kansas

Lease Name: Flax Well No. 1

Location: C NW SW Sec. 25 Twp. 16 Rge. 25 (E)(W) X

County Ness Total Depth 1986' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rice was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sc HA5 cement plug at 1635'.

thru drill pipe. WOC 2 hrs. Check top of cement with drill pipe.

Displace 150 sc of 50-50 poz cement with 4% additional gel, from

top of cement plug to base of usable water, thru drill pipe.

Mud to 420' and circulate 150 sc 50-50 poz cement-4% additional gel
thru drill pipe to base of cellar. Plug rat hole with 2 sc cement.

Very truly yours,
L. F. Massey
Conservation Division Agent