

State of Kansas



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RDV. 16 1967
 J. E. 3-20
 11-22

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Brooks of Geo. Ablah, Et al has this date requested permission to plug the following described well:

Mr. Brooks guarantees payment of the plugging fee.

Operator's full Name: George J. Ablah, Et al

Complete Address: 8028 Cork, Wichita, Kansas

Lease Name: Taylor Well No. 1

Location: App. C NW NW Sec. 24 Twp. 16 Rge. 25 (E)(W) X

County: Ness Total Depth 4600 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brooks was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 960' and displace
70 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sc cement thru drill pipe, Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with
2 sc cement.

Very truly yours,

Rev. F. Murray
 Conservation Division Agent