



15-101-20042-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1972
11-06-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Warren Davis of Hellar Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: John Eaton,

Complete Address: Shields, Kansas.

Lease Name: Shramek Well No. 1

Location: CSE-SE Sec. 36 Twp. 18 Rge. (E)(W) 27

County: Lane Total Depth 4600' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Davis was instructed to plug the well as follows:

253'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 525'.

Circulate hole with heavy mud. Pull DP to 750' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

A. L. D. Nichols
Conservation Division Agent