

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33277
Name: Cooper Service
Address 1: PO Box 381
Address 2: _____
City: Winfield State: Ks Zip: 67156 + _____
Contact Person: Albert L. Cooper
Phone: (316) 204 0072
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Layton Depth to Top: 2340 Bottom: 2368 T.D. 2377
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 035-20749-00-00
Spot Description: SW/NE/NE
SW NE NE Sec. 24 Twp. 32 S. R. 4 East West
4,096 Feet from North / South Line of Section
870 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Cowley
Lease Name: Magnusson Well #: 5
Date Well Completed: 3/3/75
The plugging proposal was approved on: _____ (Date)
by: Jeff Klock (KCC District Agent's Name)
Plugging Commenced: 12/5/11
Plugging Completed: 12/27/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Layton	oil	Surface	7"	150'	0
		Production	4 1/2"	2377'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RIH w/workstring circ various bridges and hole clean @ 1375', layed down workstring. RIH w/rubber plug @ 1303'. 12/7/11, tagged plug @ 1303'. RIH w/wireline shot squeeze holes @ 1250'-1251'. 12/13/11, RIH w/tbg. @ 1250, Butler Bros. mixed and pumped 10sxs class A common & displaced in csg. Tagged cement @ 1190' RIH w/wireline shot squeeze holes @ 256', 12/27/11, Butler Bros. pumped 110 sxs slurry mix less 10% sand from 256'-0', cment circ. . Plugging down @ 12 pm 12/27/11. Daniels Ready Mix ticket #023550.

Plugging Contractor License #: 33277 Name: Cooper Service Co.
Address 1: PO Box 381 Address 2: _____
City: Winfield State: Ks Zip: 67156 + _____
Phone: (316) 204 0072
Name of Party Responsible for Plugging Fees: Albert L. Cooper, Paid
State of Ks County, Cowley , ss.

Albert L. Cooper Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Albert L. Cooper

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAR 16 2012
KCC WICHITA