

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32864
Name: XTO Energy, Inc.
Address 1: 210 Park Avenue ; Suite 2350
Address 2: _____
City: Oklahoma City State: OK Zip: 73102 + _____
Contact Person: Karen Byers
Phone: (405) 319-3212
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Council Grove Depth to Top: 2750' Bottom: 2866' T.D. 3002'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 093-20351 • 00 • 00
Spot Description: _____
SW - SE - NE - SW Sec. 2 Twp. 24 S. R. 36 East West
1530 1518 Feet from North South Line of Section
2140 3073 Feet from East West Line of Section
GPS - KCC
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Kearny
Lease Name: Barricklow Well #: 1-2-2
Date Well Completed: 2/25/77
The plugging proposal was approved on: 3/12/12 (Date)
by: Ken Jehlik (KCC District Agent's Name)
Plugging Commenced: 3/12/12
Plugging Completed: 3/13/12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	526'	NONE
		Production	4 1/2"	3000'	888'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Existing CIBP @ 2695' w/ 2 sks cement ,Run in hole w/ 2 3/8" tbg & tag existing CIBP , circ hole w/ mud & spot 10 sks Class "C" cement up to 2547'. Pull up hole w/ tbg @ 1950' . Mix & pump 30 sks Class "C" w/ 25 lbs cottonseed hulls up to 1507', POH w/tbg .Install 4 1/2" pull sub , cut & pull 4 1/2" csg from 888' (27 jts). TIH w/ tbg @ 888' , mix & spot 150 sks Class "C" cement up to 335'. POH w/ tbg & Top out w/ 20 sks cement 64' - 4'.

Plugging Contractor License #: 33338 Name: Orr Enterprises, Inc.
Address 1: P.O. Box 1706 Address 2: _____
City: Duncan State: Oklahoma Zip: 73534 + 1706
Phone: (580) 467-0258
Name of Party Responsible for Plugging Fees: XTO Energy, Inc.
State of Oklahoma County, Oklahoma , ss.
Karen Byers (Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Karen Byers

Mall to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

MAR 20 2012

KCC WICHITA