

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form cannot be Signed  
All blanks must be Filled

OPERATOR: License #: 9228  
 Name: Marlin Oil Corporation  
 Address 1: PO Box 14630  
 Address 2: \_\_\_\_\_  
 City: Oklahoma City State: OK Zip: 73113  
 Contact Person: W.R. (Nick) Lynn  
 Phone: (405) 478-1900

Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (if needed attach another sheet)  
Toronto Depth to Top: 4252 Bottom: 4342 T.D. 7600  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 189-22663.00.00  
 Spot Description: \_\_\_\_\_  
N. N2 NW Sec. 11 Twp. 35 S. R. 36  East  West  
660 612 Feet from  North  South Line of Section  
1320 1304 Feet from  East  West Line of Section  
GPS-KCC  
 Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
 County: Stevens  
 Lease Name: Don Hall Well #: 1-11  
 Date Well Completed: \_\_\_\_\_  
 The plugging proposal was approved on: 1-26-12 (Date)  
 by: Mike Meyer (KCC District Agent's Name)  
 Plugging Commenced: 1-30-12  
 Plugging Completed: 1-31-12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
<u>Council Grove 8160 (800)</u>	<u>water</u>	-			
<u>Toronto 4252 (90)</u>	<u>gas</u>	<u>- Surface</u>	<u>8 5/8"</u>	<u>1664'</u>	<u>-0-</u>
<u>Lansing 4446 (111)</u>	<u>gas, water</u>	<u>production</u>	<u>4 1/2"</u>	<u>4650'</u>	<u>2570'</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom) to (top) for each plug set.

Marlin Oil set CIBP @ 4210' w/ 25sk cmt on top + loaded hole w/ mud. Shot + pulled 4 1/2 @ 2570' placed plugs as follows: 50sk cmt 1680'-1515', 40sk cmt 580'-445', 10 SKS. cmt 40'-0' with mud spacing each plug. Cut + Cap 8 5/8 4' below GK.

Plugging Contractor License #: 32833 Name: Sargent + Littard Casing Pulling Inc.  
 Address 1: PO Box 1450 Address 2: \_\_\_\_\_  
 City: Woodward State: OK Zip: 73801 + 1460  
 Phone: (580) 254-1881

Name of Party Responsible for Plugging Fees: Marlin Oil Corp.  
 State of Oklahoma County: Oklahoma  
W.R. Lynn (Print Name)  Employee of Operator or  Operator on above-described well.

being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: \_\_\_\_\_

Mail to: KCC - Conservation Division, 138 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
MAR 21 2012  
KCC WICHITA