

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 4058
Name: American Warrior INC
Address 1: P.O.Box 399
Address 2: _____
City: Garden City State: KS Zip: 67846 + _____
Contact Person: Kevin Wiles SR
Phone: (620) 275-2963
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Miss Depth to Top: 4964 Bottom: 4972 T.D. 5380
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 033-21,054-0000
Spot Description: NW. Sec. 27-33s-18w
C SE SE NW Sec. 27 Twp. 33 S. R. 18 East West
2340 2338 Feet from North / South Line of Section
2360 2946 Feet from East / West Line of Section
GPS-KCC
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Comanche
Lease Name: L.Deewall Well #: 1
Date Well Completed: 3-28-01
The plugging proposal was approved on: 3-12-12 (Date)
by: Ken Jehlik (KCC District Agent's Name)
Plugging Commenced: 3-14-12
Plugging Completed: 3-15-12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	664	None
		Production	4-1/2'	5550'	3000'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 4910' dump 2 sks cement on plug, cut 4-1/2" csg off @ 3000', lay down csg. ran 2-3/8" tbg, to 1040' pump 15 sks gel & 50 sks cement, pull tbg, to 700' pump 50 sks. cement, pull tbg, to 40', pump, 15 sks, pull rest of tbg, top off casing w/ 5 sks, (cement was 60/40 poz, 4% gel), cut off 8-5/8" 6' below GL & capped, fill cellar.

Plugging Contractor License #: 99996 Name: Allied cementing Co.
Address 1: P.O.Box 31, Address 2: _____
City: Russell State: KS Zip: 67665 + 0031
Phone: (785) 483-2627
Name of Party Responsible for Plugging Fees: American Warrior INC
State of Kansas County, Comanche, ss.
Kevin Wiles SR Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

MAR 21 2012

KCC WICHITA