

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34318
Name: Berexco, L.L.C.
Address 1: P. O. Box 723
Address 2: 2020 N Bramblewood, Wichita KS 67201
City: Hays State: KS Zip: 67601 +
Contact Person: Bruce Meyer
Phone: (785) 265-3311
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 4524 Bottom: 4531 T.D. 4531
Ft Scott Depth to Top: 4426 Bottom: 4429 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 135-22830 - 00 - 00
Spot Description: _____
NW NE SW _____ Sec. 3 Twp. 16 S. R. 25 East West
3-300 2310 Feet from North South line of Section
3-300 3630 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ness
Lease Name: Harold Well #: 3
Date Well Completed: 6-18-85
The plugging proposal was approved on: 3-14-12 (Date)
by: Richard Lacey (KCC District Agent's Name)
Plugging Commenced: 3-14-12 12:00 P.M.
Plugging Completed: 3-14-12 6:00 P.M.

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Mississippi	Oil/Water	8 5/8	8 5/8	341	0
Ft Scott	Oil/Water	4 1/2	4 1/2	4524	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Back off tubing at 2647', pull. Perforate 800' 2 holes. Run tubing to 2647'. Spot 10 sacks gel w/200# of hulls, 40 sacks cement, pull up to 1950', spot 30 sacks cement. Pull to 800', circulate cement to surface with 60 sacks cement. Shut in 4 1/2 pump 50 sacks cement at 400#, try to circulate up 8 5/8, no circulation. Pull tubing, top off 4 1/2 with 25 sacks cement. Hook up 8 5/8, pump 20 sacks cement 500# PSIG. Top off 4 1/2 w 15 sacks cement. Done at 6:00 p.m. Used 240 sacks 60/40 pos w 4% gel.

Plugging Contractor License #: 34318 Name: Berexco, L.L.C.
Address 1: P. O. Box 723 Address 2: 2020 N Bramblewood, Wichita KS 67201
City: Hays State: KS Zip: 67601 +
Phone: (785) 265-3311
Name of Party Responsible for Plugging Fees: Berexco, L.L.C.
State of Kansas County, Sedgwick, ss.
Curtis Gabel (Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Curtis Gabel

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAR 19 2012
KCC WICHITA

AR