

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 32278  
Name: Tengasco, Inc.  
Address 1: PO Box 458  
Address 2: 1327 Noose Rd.  
City: Hays State: KS Zip: 6601 + 9744  
Contact Person: Gary Wagner  
Phone: ( 785 ) 625-6374  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
LKC Depth to Top: 3489' Bottom: 3674' T.D. \_\_\_\_\_  
Marmaton Depth to Top: 3797' Bottom: 3807' T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 051-21331 · 00 · 00  
Spot Description: \_\_\_\_\_  
C N/2 SE NE Sec. 34 Twp. 12 S. R. 20  East  West  
3,630 Feet from  North /  South Line of Section  
660 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Ellis  
Lease Name: Schneller Well #: 3  
Date Well Completed: 8-9-1977  
The plugging proposal was approved on: 2-24-12 (Date)  
by: Rich Williams (KCC District Agent's Name)  
Plugging Commenced: 3-9-12  
Plugging Completed: 3-9-12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	289'	N/A
		Production	4-1/2"	3874'	N/A

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed, the plug or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tbg to 3454'. spotted 50 sx on bottom, pulled tbg to 3014' & mixed 100 sx w/ 300# hulls, pulled tbg to 1632' & mixed 70 sx w/ 200# hulls to circ cmt. Pulled tbg. Squeezed csg to 400 PSI w/ 40 sx. Mixed 10 sx to pres 8-5/8". 270 total sx 60/40 poz 4% gel & 500# hulls.

Plugging Contractor License #: 32332 Name: Fischer Well Service  
Address 1: PO Box 733 Address 2: \_\_\_\_\_  
City: Hays State: KS Zip: 67601 + 0733  
Phone: ( 785 ) 628-3837  
Name of Party Responsible for Plugging Fees: Tengasco, Inc.  
State of Kansas County, Ellis, ss.  
Gary Wagner  Employee of Operator or  Operator on above-described well.  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Gary Wagner

AK