


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-009-06276-00-00  
**WELL PLUGGING RECORD**

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Barton County. Sec. 32 Twp. 18 Rge. 14 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines 100' W of NE NW NE  
Lease Owner Colorado Oil & Gas Corporation  
Lease Name Skolaut Well No. 1  
Office Address Colo-Derby Building - Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 26 19 61  
Application for plugging filed November 26 19 61  
Application for plugging approved November 26 (verbally) 19 61  
Plugging commenced November 26 19 61  
Plugging completed November 26 19 61  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3543 Feet  
Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	531'	8 5/8"	531	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud from total depth to surface. Pumped 100 sacks of cement with plug into hole by Halliburton Oil Well Cementing Company.

DEC 23 1961  
12-13-61  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Harms-Burt Drilling Company  
Address P.O. Box 488 Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
ALLAN HARMS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allan Harms  
P.O. Box 488 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6 day of December, 19 61

Mary E. Van Pelt  
Notary Public.

My commission expires 1-20-62

15-009-06276-0502

DRILLERS LOG

Company: Colorado Oil & Gas Corporation 100' W of NE NW NE Section 32-18-14W  
Farm: Skelout # 1 Barton County, Kansas  
Commenced: November 17, 1961 Completed: November 26, 1961

Elevation: 1899 KB

888 - 930 anhydrite  
930 - 1210 red bed & shale  
1210 - 1560 shale & shells  
1560 - 1835 shale & lime  
1835 - 2300 lime & shale  
2300 - 2720 shale & lime  
2720 - 3042 lime & shale  
3042 - 3142 lime  
3142 - 3146 Hoebner  
3146 - 3175 lime  
3175 - 3220 shale  
3220 - 3495 lime  
3495 - 3526 Conglomerate  
3526 - 3543 Arbuckle  
3543 Total depth

RECEIVED  
STATE OF KANSAS COMMISSION  
DEC 23 1961  
CONSERVATION DIVISION  
Wichita, Kansas

Top: Hoebner - 3142  
Brown lime - 3220  
Conglomerate - 3495  
Arbuckle - 3526

Drill Stem Tests: #1 3221 - 3242 Open 1 hour. Shut in 30 min.  
Recovered 20' mud.  
IRMP-1153# FBMP-1111#  
IFP-29# FFP-44#

#2 3242 - 3275 Open 2 hours. Shut in 30 min.  
Recovered 540'-50' slightly  
oil & gas out mud. 50' heavily  
oil & gas out mud.  
IRMP-620# FBMP-235#  
IFP-35# FFP-50#

#3 3367 - 3387 Open 2 hours; 30 min.  
Shut in 30 min. Recovered  
240' salt water.  
IRMP-1190# FBMP-965#  
IFP-44# FFP-148#

Ran electric log.

Dry, plugged and abandoned

A F F I R A T I O N

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON )

I, Allan Harms of the Harms-Burt Drilling Company being first duly sworn on oath state:  
I have knowledge of the facts, statements and matters herein contained and the same are  
true and correct.

Allan Harms  
Allan Harms

Subscribed and sworn to before me this 6 day of December, 1961.

My commission expires January 20, 1962.

Mary E. Van Pelt  
Mary E. Van Pelt Notary Public