

15-101-20649-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Lane SEC. 22 TWP. 17S RGE. 27 XE/W
Location as in quarters or footage from lines:
C N $\frac{1}{2}$ NE $\frac{1}{4}$ NE $\frac{1}{4}$

Lease Owner Ol mpic Petroleum Company
Lease Name Atwell Well No. 7
Office Address 2121 So. Columbia, Tulsa, Oklahoma 74114
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed June 11, 1982
Application for plugging filed _____
Plugging commenced June 11, 1982
Plugging completed June 11, 1982
Reason for abandonment of well or producing formation _____
Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor
Producing formation _____ Depth to top _____ bottom _____ T.D. 4650
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	Surface	0	334	8 5/8	326	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Hole plugged with 50/50 pozmix, 4% gel, 3% CaCl,
as follows:
70 sacks @ 1020'
40 sacks @ 300'
10 sacks @ 40' - solid bridge
10 sacks in rathole
10 sacks in mousehole

STAFF ROOM
JUN 24 1982
Wichita Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor _____

STATE OF KANSAS COUNTY OF Sedgwick, ss. on behalf of contractor
John Jay Darrah, Jr. ~~(employee of owner or owner or operator)~~ of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.
By [Signature] Maland Drilling Co., Inc.
(Signature) 405 Century Plaza
Wichita, (Address) Ks. 67202

SUBSCRIBED AND SWORN TO before me this 15th day of June, 19 82

[Signature]
Dianne R. Fowler, Notary Public.

My Commission expires: August 25, 1984

15-101-20649-00-00

DRILLERS LOG

COMPANY: Olympic Petroleum Company
CONTRACTOR: MALLARD DRILLING CO., INC.
405 Century Plaza
Wichita, Kansas 67202

WELL NAME: #7 Merritt Atwell
DESCRIPTION: C N $\frac{1}{2}$ NE $\frac{1}{4}$ NE $\frac{1}{4}$
Sec. 22-17S-27W

RIG NO.: 1
TOTAL DEPTH: 4650

COUNTY: Lane
ELEVATION: 2679

COMMENCED: June 1, 1982

COMPLETED: June 11, 1982

CASING RECORD:
8 jts. 8 5/8" 24# surface

D & A


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>	
Surface soil, Shale	0	1330	Ran 326' new 24# 8-5/8" surface casing; set and cemented at 334' with 200 sacks common cement, 3% CaCl, 2% gel. Cement circulated. Plug down @ 4:15 P.M., June 1, 1982 Ran 5 DSTs	
Shale, Sand, Shale	1330	2084		
Anhydrite	2084	2117		
Sand and Shale	2117	2345		
Shale	2345	2725		
Lime and Shale	2725	4032		
Lime	4032	4520		
Lime and Shale	4520	4650		

Hole plugged with 50/50 pozmix, 4% gel, 3% CaCl, as follows:
70 sacks @ 1020', 40 sacks @ 300',
10 sacks & solid bridge @ 40',
10 sacks in rathole and 5 in mousehole. Plugging completed at 5:00 p.m., June 11, 1982.


RECORDED
STATE CORPORATION COMMISSION
JUN 22 1982
CONSERVATION DIVISION
Wichita Kansas

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS.

I, JOHN JAY DARRAH, JR. of MALLARD DRILLING CO., INC., certify that this is a true and correct copy of the log of the #7 Merritt Atwell well, to the best of my knowledge.


John Jay Darrah, Jr., President

SUBSCRIBED AND SWORN to before me this 15 day of June, 1982.


Dianne R. Fowler, Notary Public

My Commission Expires:
August 25, 1984