

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Russell

WELL NUMBER #1

_____ Ft. from S Section Line

_____ Ft. from E Section Line

SEC. 21 TWP. 17S RGE. 24W (E) or (W)

COUNTY Lane

LEASE OPERATOR Whitetail Crude, Inc

ADDRESS P O Box 544, Ness City, KS 67560

PHONE#(785) 798-3641 OPERATORS LICENSE NO. 31627

Date Well Completed 11/6/87

Character of Well Oil

Plugging Commenced 12/17/98

Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12/17/98

The plugging proposal was approved on 12/16/98 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filled? yes if not, is well log attached? _____

Producing Formation Kansas City/Lansing Depth to Top 4144 Bottom 4219 T.D. 4649

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Kansas City	oil			8 5/8	302	---
Lansing	oil			4 1/2	4649	---

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug is used, state the character of same and depth placed, from _____ feet to _____ feet each set. Alternate II was done from 2100' to surface. 12/17/98 Mixed 25 sacks of 60/40 6% gel + 350# of hulls. Then mixed 11 sacks of gel for a spacer with 50# of hulls. Then mixed 170 sacks of cement, pumped down and shut in @ 400 PSI. Mixed 10 sacks for the backside and shut in @ 500 PSI

Name of Plugging Contractor Allied Cementing Co Inc License No. _____

Address P O Box 31, Russell, KS 67665 12-28-98


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Whitetail Crude, Inc

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, president of Whitetail Crude, Inc (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) Mike J. Fritzler

(Address) P O Box 544, Ness City, KS 67560-0544



SUBSCRIBED AND SWORN TO before me this 22nd day of December, 1998

Debra Kerr
Notary Public Debra Kerr

My Commission Expires: 4/20/2001

USE ONLY ONE SIDE OF EACH FORM