

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-20876-00-00

LEASE NAME E. Joe

WELL NUMBER #1

4290 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 15 TWP. 17S RGE. 27 (X) or (W)

COUNTY Lane

Date Well Completed 11-21-1983

Plugging Commenced 1-14-2002

Plugging Completed 1-17-2002

RECEIVED

MAR 19 2002

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA
LEASE OPERATOR Mull Drilling Company, Inc.

ADDRESS P.O. Box 2758, Wichita, KS 67201

PHONE# (316) 264-6366 OPERATORS LICENSE NO. 5144

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-03-01 (date)

by W. Scott Alberg (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Cherokee Depth to Top 4518 Bottom 4569 T.D. 4660'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Cherokee	Oil & Water	Surface	312	8 5/8"	312	None
Lansing KC	Water	Surface	4658	4 1/2"	4658	None

RECEIVED
RECEIVED
KCC WICHITA
KCC WICHITA

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MIRU MDC DDP. Peak Wireline set CIBP @ 4125'. put 2 sx cmt on top of CIBP. RIH w/open end tbg to 2100'. Swift Services pumped 112 sxs 60/40 poz cmt w/6% gel & 100# hulls. TOOH w/tbg. Pressured up to 600# on braden head & held. Topped off 4 1/2" csg w/28 sx cmt & 200# hulls. Job witnessed by KCC Mike Maier. Swift Services pumped 25 sx 60/40 poz w/6% gel, cmt to surface.
(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Swift Services, Inc. License No. 32382

Address P.O. Box 466, Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mull Drilling Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Nancy I. Stiner (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Nancy I. Stiner

(Address) P.O. Box 2758, Wichita, KS 67201

SUBSCRIBED AND SWORN TO before me this 18th day of March, 2002

TANNIS L. TRITT
Notary Public - State of Kansas
My Appt. Expires 3-26-2003

Tannis L. Tritt
Notary Public

My Commission Expires: 3-26-2003



Services, Inc.

CHARGE TO: Well Dig. Co.
ADDRESS
CITY, STATE, ZIP CODE

TICKET No. 4273

WELL PROJECT NO. #1

LEASEE: E. Joe

CONTRACTOR: Co. Tools

WELL TYPE: Oil

WELL CATEGORY: Warehouse

JOB PURPOSE: Plug To Abandon

INVOICE INSTRUCTIONS

COUNTY/PARISH: Leve

RIG NAME/NO.

STATE: KS

CITY

DELIVERED TO: Location

DATE: 1-15-02

ORDER NO.

WELL LOCATION

SHIPPED VIA: TRUCK

WELL PERMIT NO.

OWNER: Same

PAGE 1 OF 1

PRICE REFERENCE	SECONDARY REFERENCE/ REPORT NUMBER	ACCOUNTING LOC ACCT DF	DESCRIPTION	QTY.	UM	QTY.	UM	UNIT PRICE	AMOUNT
575			MILEAGE ⁷² /103	30	mi			2.50	75.00
576			Lease Service	1	ea			500.00	500.00
581			Service Charge	225	sh			1.00	225.00
583			Drayage	281.34	mb			0.25	70.34
328			6040 lbs 68 Gal	140	sh			5.00	700.00
275			Hulls	300	lb			0.30	90.00

RECEIVED
MAR 19 2002
KCC WICHITA

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY provisions.
MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

REMIT PAYMENT TO:
SWIFT SERVICES, INC.
P.O. BOX 466
NESS CITY, KS 67560
785-798-2300

SURVEY
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?
WE UNDERSTOOD AND MET YOUR NEEDS?
OUR SERVICE WAS PERFORMED WITHOUT DELAY?
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?
ARE YOU SATISFIED WITH OUR SERVICE?

PAGE TOTAL 1,846.52
TAX 92.93
TOTAL 1939.44

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.
SWIFT OPERATOR: [Signature] APPROVAL: [Signature]
Thank You!

JOB LOG

SWIFT Services, Inc.

DATE 1-15-02 PAGE NO. 1

CUSTOMER Mall Dely Co Inc. WELL NO. #1 LEASE E. Joe JOB TYPE Plug In Abandon TICKET NO. 4223

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	0900							On loc. set up trucks
	0915							Start mixing 60/40 Poz 6% Gel
								Tubing @ 2096'
								Mix 12 ^{55'} Dump 100 [±] Halls in end
	0950							112 sks mixed shut down
	11:00							pull tubing out of hole.
								hoist up to Birden head
							600	Press. to 600 psi holding
	12:30							wait on cement in 4 1/2 to set
								top off 4 1/2 28 sks cont. 2 1/2 sks Halls
								wash and rack up trucks
								Job Complete

RECEIVED
MAR 19 2002
KCC WICHITA