

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-101-21,205 ~~00-00~~

LEASE NAME Massey

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 15 TWP. 17S RGE. 27W (E) or (W)

COUNTY Lane

Date Well Completed

Plugging Commenced 6-14-96

Plugging Completed 6-14-96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Brito Oil Company, Inc.

ADDRESS 120 S. Market, Ste. 300 Wichita, Ks. 67202

PHONE (316) 263-8787 OPERATORS LICENSE NO. 4629

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Kevin Stroub (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 4660'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	219'	None
				4-1/2"	4658'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from feet to feet each side.
Plug Job Only - No Pipe Recovery. Pumped 200# hulls, 25 sacks cement, 11 sacks gel, 105 sacks cement down the 4-1/2" casing. Pressured to 1000#, Shut in @800 PSI. Pumped 15 sacks cement down backside, pressured to 400#, shut in @400 PSI, 60/40 Pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brito Oil Company, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed with the State Corporation Commission, and that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 21st. day of June, 1996

[Signature]
 Notary Public

My Commission Expires:

