

15-101-20755-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Lane SEC. 19 TWP. 17 RGE. 27 N/W
 Location as in quarters or footage from lines:
SW/NE/SW

Lease Owner Landmark Oil Exploration, Inc.
 Lease Name Collins Well No. #1
 Office Address 105 S. Broadway, Suite 1040 - Wichita, Ks.
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced May 23, 1983
 Plugging completed June 8, 1983
 Reason for abandonment of well or producing formation Depleted

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Benny Beck

Producing formation _____ Depth to top _____ bottom T.D. 4650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	375'	NONE
				5 1/2"	4649'	2533.99'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Dumped sand to 3850' and five (5) sacks cement.
 Shot pipe @ 3800', 3000' and 2700. Shot pipe @ 2500'.
 Pulled sixty-three (63) joints 5 1/2" casing.
 Squeezed well with two (2) sacks hulls, ten (10) sacks gel, fifty (50)
 sacks 60/40 pozmix cement with 2% added gel and 3% calcium chloride,
 ten (10) sacks gel, fifty (50) sacks cement, fifteen (15) sacks gel,
 one (1) sack hulls, released plug, pumped one hundred (100) sacks
 60/40 pozmix cement with 2% added gel and 3% Calcium Chloride.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
 JAMES W. ROCKHOLD - Box 698 - Great Bend, Ks.
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 20th day of June, 19 83



Margaret Prosser
 Notary Public.
 RECEIVED
 STATE CORPORATION COMMISSION

My Commission expires _____

JUN 21 1983

CONSERVATION DIVISION
 Wichita, Kansas