

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-101-2007100-00
API NUMBER Unknown

LEASE NAME Collins

WELL NUMBER # 4

SPOT LOCATION NW NW SW

SEC. 18 TWP. 17 RGE. 27 (X) or (W)

COUNTY Lane

Date Well Completed 10-31-73

Plugging Commenced 5-9-85

Plugging Completed 5-10-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR American Warrior, Inc.

ADDRESS Hwy. 50 West, P.O. Box 399, Garden City,
Ks. 67846

PHONE # (316) 275-7461 OPERATORS LICENSE NO. 4058

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation none Depth to top none bottom none T.D. 4620

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Kansas City	Oil	4194	4202	4 1/2"	none	none
Pawnee	"	4408	4413	4 1/2"	none	none
Fort Scott	"	4490	4512	4 1/2"	none	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Squeezed Cedar Hills section w/ 425 sacks 60/40 pos. 3% calcium chloride 6% gel. Finished plugging well down casing w/ 450 sacks of 60/40 pos. 3% calcium chloride 6% gel 30 sacks gel 19 sacks hulls - plugged to surface. Started plug at 2100' and plugged to surface. Pressured up on backside - 400 lbs.-Held.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287
Address Ness City, KS


STATE OF KANSAS COUNTY OF ELLIS, ss.

Isaidore P. Kisner (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) Isaidore P. Kisner
(Address) 3000 Broadway Avenue, Suite C
P.O. Box 1084
Hays, KS 67601-1084

SUBSCRIBED AND SWORN TO before me this 11 day of Sept., 19 85

RECEIVED
STATE CORPORATION COMMISSION
Notary Public
Rosalind A. King
ROSALIND A. KING



My Commission expires: May 28, 1989

SEP 13 1985

CONSERVATION DIVISION

Form CP-4
Revised 01-84