

15-101-20175-00-00

FORM CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

WELL PLUGGING RECORD

Lane _____ County. Sec. 30 Twp 17S Rge. XXK) 27 (W)

Location as "NE/CNW&SW" or footage from lines. NE NE SW

Lease Owner Beren Corporation

Lease Name Harlamert "B" Well No. 1

Office Address 970 Fourth Financial Center Wichita, KS 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed April 17 1976

Application for plugging filed (verbally) April 17 1976

Application for plugging approved (verbally) April 17 1976


Plugging commenced April 17 1976

Plugging completed April 17 1976

Reason for abandonment of well or producing formation No commercial quantity of oil or gas encountered.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plot

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4670'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	342.87	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug set @ 850' with 70 sx. cement
2nd plug set @ 350' with 20 sx. cement
3rd plug set @ 40' with 10 sx. cement
State Plugger: Gilbert Balthazor
Plug was down @ 8:00 a.m. April 17, 1976

Name of Plugging Contractor Abercrombie Drilling, Inc. (If additional descriptions necessary, use BACK of this sheet)
Address 801 Union Center Wichita, Kansas 67202


STATE OF Kansas COUNTY OF Sedgwick ss.
Jerry A. Langrehr-Exec. V.P. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr
801 Union Center Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 23rd day of April, 19 76

My commission expires February 18, 1980
Diane Steincamp Notary Public.



APR 27 1976
CONSERVATION DIVISION
WICHITA, KANSAS

CONTRACTOR'S WELL LOG

15-101-2017S-00-00

OPERATOR: Beren Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: HARLAMERT "B" #1
 LOCATION: NE NE SW Section 30-17S-27W Lane County, Kansas
 SPUD DATE: April 6, 1976
 COMPLETION DATE: April 17, 1976

0	150	Top Soil & Sand
150	347	Shale & Sand
347	804	Sand-Shale
804	1550	Shale
1550	2075	Shale & Sand
2075	2110	Shale
2110	2150	Anhydrite
2150	2950	Shale
2950	3160	Shale-Sand
3160	3365	Shale
3365	3579	Shale & Lime
3579	3880	Lime & Shale
3880	4030	Shale & Lime
4030	4530	Lime
4530	4593	Lime & Shale
4593	4632	Lime
4632	4670	Lime & Shale
	4670	Rotary Total Depth

Drilled 347' of 12½" hole. Ran 7 jts. used 8 5/8" casing. Tallied 334.87', Set @ 342.87' Cemented with 200 sx. 60/40 Posmix, 3% ca. cl. 2% gel, followed by 25 sx. regular Common, 2% gel, 3% ca. cl. Halliburton Cement. Cement did Circulate. 3 hours for welding collars. Plug was down @ 7:25 p.m. April 6, 1976.

PLUGGED AND ABANDONED: 1st Plug was Set @ 850' with 70 sx. cement
 2nd Plug was Set @ 350' with 20 sx. cement 3rd Plug was Set @ 40' with 10 sx. cement
 State Plugger: Gilbert Balthazor - Plug was down @ 8:00 a.m. April 17, 1976.

SAMPLE TOPS: Anhydrite 2110'
 B/Anhydrite 2150'

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the HARLAMERT "B" #1 NE NE SW Section 30-17S-27W Lane County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
 Jerry A. Langrehr, Exec. V.P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 22nd day of April, 1976.

Diane Steincamp
 Diane Steincamp - Notary Public

My Commission Expires: February 18, 1980.

