

15-101-20734-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED Form CP-4
STATE CORPORATION COMMISSION PERMISSION-15-80

DEC 3 1982

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Lane SEC. 30 TWP. 17S RGE. 27 E/W
Location as in quarters or footage from lines:
440' FSL & 440' FEL SE/4 Sec. 30-17S-27W

Lease Owner Chief Drilling Co., Inc.
Lease Name Neeley Well No. #1
Office Address 905 Century Plaza Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry
Date Well Completed 11-23-82
Application for plugging filed 11-23-82
Plugging commenced 11-23-82
Plugging completed 11-23-82
Reason for abandonment of well or producing formation dry hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation none Depth to top bottom T.D.
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	8 jts. 322'			8 5/8"	set @ 321'	

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from feet
to feet for each plug set.
Plugged w/35 sx. @ 1880' 50 sx. @ 1200', 35 sx. @ 380'
10 sx. @ 40', 10 sx. in rat hole, 10 sx. in mouse hole,
150 sx. total 50-50 pos mix, 2% gel, 3% c.c. started @
9:00 a.m. completed @ 12:45 p.m. state pluggger Steve Durrant

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Warrior Drilling Co., Rig # 2 Lic. # 5883

STATE OF Kansas COUNTY OF Sedgwick, ss.
F.W. Shelton, Jr. (employee of owner) ~~or (owner or operator)~~ of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) F.W. Shelton, Jr.
F.W. Shelton, Jr.,
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of November, 19 82

STATE OF KANSAS
NOTARY PUBLIC
MARTHA E. GUSTIN

Martha E. Gustin
Martha E. Gustin Notary Public.

My Commission expires: 4-15-85

WELL LOG

15-101-20734-00-00

CHIEF DRILLING CO., INC.
905 Century Plaza
Wichita, Kansas 67202

NEELEY #1
440' FSL & 440' FEL SE/4
SEC. 30-17S-27W LANE COUNTY,
KANSAS

CONTRACTOR: Warrior Drilling Co., Rig #2
CASING RECORD: Ran 8 jts. new 20# , 322', set
@ 331', cemented w/190 sx. common 3% c.c., 2% gel

COMMENCED: 11-14-82
COMPLETED: 11-23-82

FORMATION	FROM	TO	ELEVATIONS
Surface Sand & Clay	0	335	2713 GR.
Clay & Sand	335	473	2717 D.F.
Sand & Shale	473	1435	2720 K.B.
Shale & Sand	1425	2115	
Anhydrite	2115	2148	
Shale	2148	2992	
Shale & Lime	2992	3608	
Lime & Shale	3608	4148	
Lime	4148	4395	
Lime & Shale	4395	4667	
RTD		4667	

D & A Plugged

RECEIVED
STATE CONSERVATION COMMISSION

DEC 3 1982

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the 440' FSL & 440' FEL SE/4 Sec 30-17S 2&W Lane, County, Kansas, to the best of my knowledge and belief.


CHIEF DRILLING CO., INC.



F. W. Shelton, Jr., Vice President

Subscribed and sworn to before me this 1st day of December, 1982.

STATE OF KANSAS
NOTARY PUBLIC
MARTHA E. GUSTIN


Martha E. Gustin, Notary Public