

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 101 15-01-20149-00-00  
 LEASE NAME Harlamert A  
 WELL NUMBER 1

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

       Ft. from S Section Line  
SE NW NW Ft. from E Section Line  
 SEC. 30 TWP. 17 RGE. 27 (E) or (W)  
 COUNTY Lane  
 Date Well Completed 6-29-75  
 Plugging Commenced 4-17-92  
 Plugging Completed 4-17-92

LEASE OPERATOR Beren Corp.  
 ADDRESS Box 723 Hays, Kansas 67601  
 PHONE#(913) 628 6101 OPERATORS LICENSE NO. 5364

Character of Well Oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-17-92 (date)  
 by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filled?        If not, is well log attached?         
 Producing Formation        Depth to Top        Bottom        T.D. 4624

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	355	8 5/8		None
	Casing	0	4619	4 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used state the character of same and depth placed, from feet to feet each set.  
Pump 500# hulls with 225 sk. cement to fill to 1300'. Plugged off while displace cement. Pressure up to 750#. Run gun down to perf. 1300' tag cement at 1150'. Perf. 1300' fill casing to surface with cement. Pump 5 sk. out perfs. at 1000#. 1/2 RPM. Hook up to 8 5/8 pump 100 sk. down surface 300# pressure  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Beren Corp. License No. 5364  
 Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Beren Corp.  
 STATE OF Kansas COUNTY OF Ellis, ss.

RECEIVED  
 STATE CORPORATION COMMISSION

APR 21 1992

Mr. Ted Crawford (Employee of Operator) CONSERVATION DIVISION  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Ted Crawford  
 (Address) Box 723 Hays, Ks. 67601  
20 day of April, 19 92  
Rosemary Smith  
 Notary Public

NOTARY PUBLIC - State of Kansas  
 ROSEMARY SMITH  
 My Commission Expires 5-1-95

My Commission Expires: 5-1-1995