

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

15-101-20746-00-00

Give All Information Completely
 Make Required Affidavit

COUNTY Lane SEC. 18 TWP. 16S RGE. 29W E/W
 Location as in quarters or footage from lines:
NE NW SW Sec. 18-16S-29W

Lease Owner Bankoff Oil CO.
 Lease Name Magie Well No. #1
 Office Address 6202 S. Lewis Suite 176 Box 3446 Tulsa, Ok.
 Character of Well (Completed as Oil, Gas or Dry Hole): D.H. 74101
 Date Well Completed 12-23-82
 Application for plugging filed 12-23-82
 Plugging commenced 12-23-82
 Plugging completed 12-23-82
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well District #1

Producing formation _____ Depth to top _____ bottom _____ T.D. 4475'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
surface	7 jts. 302'	new	20#	8 5/8"	set @ 311'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged w/110 sx. 50-50 pos mix, 4% gel, 3% c.c., plug set @ 1380' w/70 sx., 330' w/40 sx., 40' w/10 sx. 10 sx. in rat hole, 10 sx. in mouse hole, started @ 3:00 p.m. completed @ 5:15 p.m.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Warrior Drilling Co., Rig #2

STATE OF Kansas COUNTY OF Sedgwick, ss.

F.W. Shelton, Jr., Vice Pres. (employee of owner) ~~or (owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

FEB 9 1983
 02-09-1983
 CONSERVATION DIVISION
 Wichita, Kansas

(Signature) F.W. Shelton, Jr.
F.W. SHELTON, JR., VICE PRES.
 (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December 19 82

MARTHA E. GUSTIN
 NOTARY PUBLIC
 STATE OF KANSAS

Martha E. Gustin
 Martha E. Gustin Notary Public.

My Commission expires 4-15-85

WELL LOG

15-101-20746-00-00

December 23, 1982

#1 MAGIE
NE NW SW 18-16S-29W
Lane County, Ks.

OPERATOR: Bankoff Oil Company
CONTRACTOR: Warrior Drilling Co., Rig #2
COMMENCED: December 15, 1982
COMPLETED: December 23, 1982

8 5/8" @ 311' w/200 sx. 60-40 pos mix

0	43	Surface clay
43	313	Sand & Clay
313	1588	Sand & Shale
1588	2187	Shale
2187	2215	Anhydrite
2215	2407	Shale
2407	3105	Shale & Lime
3105	3679	Lime & Shale
3679	4253	Shale & Lime
4253	4475	Lime
	4475	RTD

D & A

We certify that the above and foregoing is a true and correct copy of the log on the #1 MAGIE, located in Lane County, Kansas.

WARRIOR DRILLING CO., RIG #2

F.W. Shelton, Jr.
F.W. Shelton, Jr., Vice President

Subscribed and sworn to before me this 23rd day of December, 1982.

Martha E. Gustin
Martha E. Gustin Notary Public

RECEIVED
STATE CORPORATION COMMISSION

FEB 9 1983
02-09-1983
CONSERVATION DIVISION
Wichita, Kansas