


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Lane _____ County. Sec. 18 Twp 16S Rge. 29 (E) (W) X
Location as "NE/CNWSW4" or footage from lines SW NE NW
Lease Owner Chief Drilling Co., Inc.
Lease Name ROEMER C Well No. #1
Office Address 905 Century Plaza Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 1-22-82 19__
Application for plugging filed 1-22-82 19__
Application for plugging approved 1-22-82 19__
Plugging commenced 1-22-82 19__
Plugging completed 1-22-82 19__
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4540 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	313'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged w/70 sx. @ 1100', 40 sx. @ 320', 10 sx. @ 40', 10 sx. in rat hole, 5 sx. in mouse hole 135 sx. total 50-50 pos mix, 6% gel 2% c.c., started @ 8:30 p.m., finished @ 11:00 p.m.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Warrior Drilling Co.
Address 905 Century Plaza Wichita, Ks. 67202

STATE OF Kansas, COUNTY OF Sedgwick ss.
F.W. Shelton, Jr., (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F.W. Shelton, Jr.
F.W. Shelton, Jr., Vice President
905 Century Plaza, Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of January, 1982

Martha E. Gustin
Martha E. Gustin Notary Public.

My commission expires _____



01-26-1982

15-101-20598-00-00

WELL LOG

CHIEF DRILLING CO., INC.
905 Century Plaza
Wichita, Kansas 67202

ROEMER C #1
SW NE NW SEC. 18-16S-29W
LANE COUNTY, KANSAS

CONTRACTOR: WARRIOR DRILLING CO.
CASING RECORD: ran 8 jts. 313' new 20# 8 5/8" set
@ 322' cemented w/200 sx. common
quick set, Plug down @ 9:00 p.m.

COMMENCED: 1-14-82
COMPLETED: 1-22-82

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATIONS</u>
			2787 GR.
Surface Sand & Clay	0	705	2791 D.F.
Clay & Sand	705	2016	2794 K.B.
Sand & Shale	2016	2191	
Anhydrite	2191	2220	
Shale	2220	3140	
Shale & Lime	3140	3738	
Shale	3738	3945	
Lime	3945	4159	
Lime & Shale	4159	4392	
Shale & Lime	4392	4421	
Lime	4421	4540	
RTD	4540		

D & A

RECEIVED
STATE CORPORATIONS COMMISSION

JAN 28 1982
01-28-1982
CONSERVATION DIVISION
Wichita Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SW NE NW SEC. 18-16S-29W LANE County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

F. W. Shelton, Jr.

F. W. Shelton, Jr., Vice President

Subscribed and sworn to before me this 27th day of January 1982.

MARTHA E. JUSTIN
NOTARY PUBLIC
7-15-82

Martha E. Justin
Notary Public