

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-101-20,442-00-00

LEASE NAME James'E'

WELL NUMBER #1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2310' Ft. from S Section Line

990' Ft. from E Section Line

SEC. 25 TWP. 16S RGE. 29W ~~XXXXX~~ W)

LEASE OPERATOR Mull Drilling Company, Inc.

ADDRESS P.O. Box 2758, Wichita, KS 67217

COUNTY Lane

PHONE (316) 264-6366 OPERATORS LICENSE NO. 5144

Date Well Completed 5/6/80

Character of Well (Depleted)

Plugging Commenced 4/24/86

(OIL, GAS OR WATER RECORDS)

Plugging Completed 4/24/86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Steve Durant  
C-10 5/8/80

Is ACO-1 filed? 5/5/86 If not, is well log attached? Yes

Producing Formation (Was Cherokee) Depth to Top 4548 Bottom 4559 T.O. 4620'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8-5/8"	320.49'	
Production				4-1/2"	4619.94'	NONE (Csg stuck in hole)

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

4/22/86 MI Plains Well Service to pull csg. Plugged perfs @ 4337-4342'  
as follows: 2 sx cmmn, 35 gal sand, 2 sx cmmn. Worked csg. Stuck in  
hole. No csg. rec. Perf 3 shots @ 1400'. Cem w/100 sx Howco Lite from 1400'  
to surf. Pmpd 60 sx Howco Lite down ann of surf pipe. P&A 10:50 AM 4/24/86  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Job by Halliburton License No.   

Address   

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Paul M. Gunzelman (Employee of Operator) ~~XXXXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein, contained and the log of the above-described well as filed that the same are true and correct. STATE CORPORATION COMMISSION EX-HELP ME GOD.

(Signature) Paul M. Gunzelman

(Address) P.O. Box 2758, Wichita 67201

MAY 08 1986  
05-08-1986  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS

TO before me this 5th day of May, 19 86

PATRICIA L. UNGLEICH  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
My Appt. Exp. 3/27/87

My Commission Expires: March 27, 1987 Notary Public Patricia L. Ungleich

15-101-20442-00-00

WELL LOG  
James E #1  
NW NE SE Sec. 25-16S-29W  
Lane County, Kansas

Name of Operator: Mull Drilling Co., Inc.  
221 N. Main - Suite 300  
Wichita, Kansas 67202

Date Completed: March 15, 1980

FROM	TO	
0	335	Surface
335	1440	Shale and Sand
1440	2010	Shale
2010	2238	Shale and Lime
2238	2470	Shale and Anhydrite
2470	4530	Shale and Lime
4530	4562	Lime
4562	4612	Shale and Lime
4612		Total Depth

STATE OF KANSAS  
COUNTY OF BARTON ss

George E. Miller, Jr., President of Blue Goose Drilling Co., Inc.,  
being first duly sworn on oath says: That I have knowledge of the facts,  
statements and matters herein contained and the log of the above described  
well as filed and that the same are true and correct.

*George E. Miller, Jr.*  
George E. Miller, Jr.

Subscribed and sworn before me this 21st day of March, 1980.

*Mary Ann Schwamborn*  
Notary Public Barton County

My commission expires 8-1-81.

