

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,584-00-00

LEASE NAME JAMES "B"

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2970' Ft. from S Section Line

330' Ft. from E Section Line

SEC. 25 TWP. 16S RGE. 29 (E) or (W)

COUNTY LANE

LEASE OPERATOR Davis Petroleum, Inc.

ADDRESS R.R. 1 Box 183 B Great Bend, KS. 67530

PHONE# (316) 793-3051 OPERATORS LICENSE NO. 4656

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 4-28-91

Plugging Commenced 4-28-91

Plugging Completed 4-28-91

The plugging proposal was approved on April 30, 1991 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4095'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surface		0	331'	8 5/8"	331'	none

JUN 10 1991
06-10-1991
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

2230' - .50 SX, 1115' -50 sx., 600' - 50 sx., 360' - 50 sx. 10 sx. - 40' & solid bridge plug
15 sx. in rathole Total: 225 SX 60/40 Pozmix, 6% Gel, 1/4# flo seal per sack

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. Drilling, Inc. License No. 6039

Address R.R. 1 Box 183 B Great Bend, KS. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Davis Petroleum, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.

Greg Davidson (Employee of Operator) or ~~(Operator)~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Greg Davidson

(Address) R.R. 1 Box 183 B Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 7th day of May, 19 91

Bessie M. DeWerff
Notary Public
Bessie M. DeWerff

My Commission Expires: 5-20-93



15-101-21584-00-00

DRILLER'S WELL LOG

COMMENCED: 4-23-91
COMPLETED: 4-30-91

DAVIS PETROLEUM, INC.
JAMES "B" #1
SE SE NE Sec. 25-16S-29W
LANE COUNTY, KS.

ELEVATION: 2789' GR 2794 KB

0 - 332 Surface
332 - 2550 Shales
2550 - 2832 Shale & Lime
2832 - 3010 Shale
3010 - 3420 Shale & Lime
3420 - 4095 Lime

FORMATION DATA: (sample)

Anhy 2194-2224
WAbunsee 3557 (-763)
Heebner 3951 (-1157)
Lansing 3989 (-1195)

SURFACE CASING:

8 5/8" set @ 331' W/190 sx. 60/40 Poz,
2% Gel, 3% CC


A F F I D A V I T

STATE OF KANSAS)
) ss
COUNTY OF BARTON)

GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson

Subscribed and sworn to before me this 7th day of June, 1991



Bessie M. DeWerff
NOTARY PUBLIC: Bessie M. DeWerff

My Commission Expires: 5-20-93

RECEIVED
STATE CORPORATION COMMISSION

JUN 10 1991

CONSERVATION DIVISION
Wichita, Kansas