

1 C70646

2-28

142

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-21,496-00-00

SW SW NW, SEC. 6, T 16 S, R 29 W/EX  
2970 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5420 & 7245

Lease Name Jasper Well # 1-6

Operator: White & Ellis Drilling, Inc. & Name &

County Lane 144.63

Address Texas-El Dorado Oil Company  
401 East Douglas, Suite 500  
Wichita, KS 67202

Well Total Depth 4450 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 357

Abandoned Oil Well Gas Well Input Well SHD Well D&A X

Other well as hereinafter indicated

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address 401 East Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 10 p.m. Day: 27 Month: 2 Year: 19 89

Plugging proposal received from Bob Kasper

(company name) White & Ellis Drilling, Inc. (phone) 316-263-1102

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2659' Anhydrite 2054-81'

1st plug at 2080' with 50 sx cement, 2nd plug at 1500' with 80 sx cement,

3rd plug at 360' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 12 a.m. Day: 28 Month: 2 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2080' with 50 sx cement,

2nd plug at 1500' with 80 sx cement,

3rd plug at 360' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(if additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

Signed Dan Goodrow (TECHNICIAN)

DATE 3-6-89

INV. NO. 24061 2-28

RECEIVED STATE CORPORATION COMMISSION

MAR 03 1989

CONSERVATION DIVISION Wichita, Kansas

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. 12 month 10 day 88 year

API Number 15-101-21,496-00-00

OPERATOR: License # 5420 7245
Name White & Ellis Drlg., Inc. & Texas-El Dorado Oil Co.
Address 401 E. Douglas, Suite 500
City/State/Zip Wichita, KS 67202
Contact Person Michael L. Considine
Phone (316) 263-1102

SW SW NW Sec. 6 Twp. 16S S. Rg. 29 East
2970' Ft. from South Line of Section
4950' Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5420
Name White & Ellis Drilling, Inc.
City/State Wichita, KS 67202

Nearest lease or unit boundary line 330' feet
County Lane

Well Drilled For: X Oil Storage Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Lease Name Jasper Well # 1-6
Ground surface elevation 2659' feet MSL

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Depth to bottom of fresh water 160' 200'
Depth to bottom of usable water 1100'

Surface pipe by Alternate: 1 2 X
Surface pipe planned to be set 310'

Conductor pipe required None
Projected Total Depth 4450' feet

Formation MISSISSIPPIAN

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 11-22-88 Signature of Operator Michael L. Considine Title Sec/Treas

For KCC Use: Michael L. Considine

Conductor Pipe Required feet; Minimum Surface Pipe Required 200' feet per Alt. X 2

This Authorization Expires 6-2-89 Approved By LKW/12-2-88

EFFECTIVE DATE: 12-7-88

310'-85/8"

NO WW

Spud 2-20-89

SW SW NW Sec. 6 Twp. 16S S. Rg. 29 East

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth (ft.), Formation, and Size (SX). Includes entries for 1st through 5th plugs and a rathole to surface minus 5 feet.

Vertical list of well details: PUSHED Bob Kasper, TD 4450, FORMATION MISSO, SURFACE PIPE 8 5/8" @ 357', ANHYDRITE 2054', ELEVATION 2659', STARTING TIME & DATE 10:41 AM - 2-27-89, COMPLETION TIME & DATE 1:00 PM - 2-27-89, 1st PLUG @ 2080 FT. W/ 50 SX, 2nd PLUG @ 1500 FT. W/ 80 SX, 3rd PLUG @ 360 FT. W/ 40 SX, 4th PLUG @ 40 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE-HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ 60/40 6% CEMENT COMPANY Hilliard, TECHNICIAN D. G.

RECEIVED STATE CORPORATION COMMISSION 03-03-1989 CONSERVATION DIVISION Wichita, Kansas

Don't see all