

1 070729

10-2

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,525-00-00

NW NW SE, SEC. 6, T 16 S, R 29 W/X

2310 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Cochran Well # 1

Operator: Chief Drilling Company, Inc.

County Lane 144.79

Name:

Address 224 East Douglas, Suite 350

Well Total Depth 4455 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 332

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Company License Number 5883

Address 151 North Main, Suite 700, Wichita, KS 67202

Company to plug at: Hour: 4 p.m. Day: 2 Month: 10 Year: 19 89

Plugging proposal received from Marion Burris

(company name) Warrior Drilling Company (phone) 316-262-3791

Elevation 2676'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2072-2103'

1st plug at 2075' with 50 sx cement, 2nd plug at 1350' with 80 sx cement,

3rd plug at 360' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Mike Spain (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 5:30 p.m. Day: 2 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2075' with 50 sx cement,

2nd plug at 1350' with 80 sx cement,

3rd plug at 360' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

XXXXXX observe this plugging.

DATE 10-11-89

Signed Dan Johnson (TECHNICIAN)

INV. NO. 26079

FORM MUST BE TYPED
FORM C-1 12/88

State of Kansas
NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 9 - 21 - 89
month day year

NW NW SE Sec 6 Twp 16 S, Rg 29 East
West

OPERATOR: License # 5886
Name: Chief Drilling Co., Inc. (White & Ellis)
Address: 224 E. Douglas, #350 / Texas-Eldorado
City/State/Zip: Wichita, KS 67202
Contact Person: Douglas W. Thimesch
Phone: 316 262-3791

2310 feet from South line of Section
2310 feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License # 5883
Name: Warrior Drilling Company

County: Lane
Lease Name: Cochran Well #: 1
Field Name: (Wildcat)

Is this a Prorated Field? yes X no

Target Formation(s): Lansing

Nearest lease or unit boundary: 330

Ground Surface Elevation: 2676 feet MSL

Domestic well within 330 feet: yes X no

Municipal well within one mile: yes X no

Depth to bottom of fresh water: 150

Depth to bottom of usable water: 1300

Surface Pipe by Alternate: 1 X 2

Length of Surface Pipe Planned to be set: 310'

Length of Conductor pipe required: None

Projected Total Depth: 4700'

Formation at Total Depth: Mississippi

Water Source for Drilling Operations:

X well farm pond other

DWR Permit #: 889021-00

Will Cores Be Taken?: yes X no

If yes, proposed zone:

If OWM: old well information as follows:

Operator:

Well Name:

Comp. Date: Old Total Depth:

Directional, Deviated or Horizontal wellbore? yes X no

If yes, total depth location:

Exp. 3/18/90

200' Alt. II Req.

AFFIDAVIT

PUSHER Warrior Drilling
TD 4445 FORMATION Pawnee
SURFACE PIPE 8 5/8 @ 332
ANHYDRITE 2072 ELEVATION 2103
STARTING TIME & DATE _____
COMPLETION TIME & DATE _____
1st PLUG @ 2075 FT. W/ 50 SX
2nd PLUG @ 1350 FT. W/ 80 SX
3rd PLUG @ 360 FT. W/ 40 SX
4th PLUG @ 400 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ _____ SX
CEMENT COMPANY _____
TECHNICIAN 11/5
TYPE OF CEMENT 60/40 6%
3:00 PM

RECEIVED
STATE CORPORATION COMMISSION

5280	1980
4950	1650
4620	1320
4290	990
3960	660
3630	330
3300	
2970	
2640	
2310	
1980	
1650	
1320	
990	
660	
330	

6 months of effective date
Spud date: OCT 05 1989
10-05-1989

RECEIVED
CORPORATION DIVISION

REMEMBER TO: VANDER

- File Drill Pit Application (form CDP-1) with Intent to Drill;
- File Completion Form ACO-1 within 120 days of spud date;
- File acreage attribution plat according to field prorations orders;
- Notify appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water.