

1 031072

4-11

109 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,546-00-00
App. SW SW NW, SEC. 16, T 16 S, R 29 W/EX

3270 ~~2846~~ ~~4270~~ feet from S section line
4670 ~~4694~~ ~~4670~~ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30324

Lease Name Kerkhoff Well # 1

Operator: South Lake Exploration

County Lane 146.25

Name & Address P.O. Box 926691

Well Total Depth 4500 feet

South Lake, TX 76092

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 328

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 1:45 a.m. Day: 11 Month: 4 Year: 19 90

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2080-2117'
1st plug at 2100' with 50 sx cement, 2nd plug at 1350' with 80 sx cement,
3rd plug at 360' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4:30 a.m. Day: 11 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement,
2nd plug at 1350' with 80 sx cement,
3rd plug at 360' with 40 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 4-25-90
SERV. NO. 27969
4-11

Signed Steve Durrant
(TECHNICIAN)

04481990

FORM MUST BE TYPED

State of Kansas

101-21,546-00-00

FORM MUST BE SIGNED

FORM C-1 12/1987

EFFECTIVE DATE: 3/29/90

NOTICE OF INTENTION TO DRILL

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well Approx.

Expected Spud Date 03 30 90 month day year

SW.. SW.. NW.. Sec 16; Twp 16 S, Rg 29.. East West

OPERATOR: License # 30324 Name: South Lake Exploration Address: P. O. Box 926691 City/State/Zip: South Lake, TX 76092 Contact Person: Terry Boroughs Phone: (817) 430-1304

2846 4270 feet from South line of Section 4694 4670 feet from East line of Section (Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 5422 Name: Abercrombie DRILLING, Inc.

County: Lane Lease Name: Kerkhoff Well #: 1 Field Name: Wildcat

Is this a Prorated Field? yes X no Target Formation(s): Mississippian Nearest lease or unit boundary: 586' Ground Surface Elevation: Unknown Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water: 175' Depth to bottom of usable water: 1150' Surface Pipe by Alternate: 1 X 2 Length of Surface Pipe Planned to be set: 300' Length of Conductor pipe required: None Projected Total Depth: 4500' Formation at Total Depth: Mississippian Water Source for Drilling Operations: X well farm pond other

Well Drilled For: Well Class: Type Equipment: X Oil Inj Infield X Mud Rotary Gas Storage Pool Ext. Air Rotary OAWD Disposal X Wildcat Cable Seismic: # of Holes

DVR Permit #: Will file Will Cores Be Taken?: yes X no

If OAWD: old well information as follows: Operator: N/A Well Name: Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no If yes, total depth location: EXP 9-23-90

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following minimum requirements will be met:

- 1. The appropriate district office shall be notified before setting surface pipe;
2. The minimum amount of surface pipe as specified above shall be set by circulating cement to the top; in all cases surface pipe shall be set through all unconsolidated materials plus a minimum of 20 feet into the underlying formation;
3. If the well is dry, a plugging proposal shall be submitted to the district office. An agreement between the operator

maley
PUSHER Harold
TD - 4500 FORMATION MISS
SURFACE PIPE 8 5/8 @ 328
ANHYDRITE 2088 ELEVATION 2177
STARTING TIME & DATE 1:45 A.M. 4-11-90
COMPLETION TIME & DATE 4:30 A.M. 4-11-90
1st PLUG @ 2100 FT. W/ 50 SX
2nd PLUG @ 1350 FT. W/ 80 SX
3rd PLUG @ 360 FT. W/ 40 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ Haul SX
CEMENT COMPANY Allied.
TECHNICIAN S-D
TYPE OF CEMENT 60/40 Poz 60%

Spud 4-2-90
Boat 8/8
C.M.
1150

- Notify appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water.