

1 060493

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW SE SE , SEC. 8 , T 16 S, R 29 (W)X
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,130-00-00

330 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5399

Lease Name Lundgren "E" Well # 1

Operator: American Energies

County Lane

Name & Address 575 Fourth Financial Center

Well Total Depth 4450 147.88 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 379

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Thunderbird Drilling, Inc. License Number 5131

Address Box 18407, Wichita, KS 67218

Company to plug at: Hour: 6:00 pm Day: 22 Month: February Year: 19 85

Plugging proposal received from Ed Cook

(company name) Thunderbird (phone) 316-685-1441

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2080' with 50 sx cement

2nd plug at 1290' with 50 sx cement

3rd plug at 430' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:00 pm Day: 22 Month: February Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2080' with 50 sx cement, 2nd plug at 1290' with

50 ss cement, 3rd plug at 430' with 50 sx cement, 4th & 5th plugs - solid bridge -

hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate

rat hole with 15 sx cement.

03-04-1985
MAR 01 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

If additional description is necessary, use BACK of this form.

Wichita, Kansas

(X) / did not observe this plugging.

DATE 3-5-85

Signed Paul A. Luthi (TECHNICIAN)

LOG. NO. 7223

2.22