

1 050696

API NUMBER 15-101-21,242-00-00

To: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION NWSE NW, SEC. 8, T 16 S, R 29 W
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

3630 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5399

Lease Name Jennison "B" Well # 1

Operator: American Energies Corp.

County Lane 147.13

Name &

Address 575 Fourth Financial Center Well Total Depth 4527 Miss feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 382

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Wheatstate Oilfield Service License Number 5149

Address P.O. Box 329 Pratt Kansas 67124

Company to plug at: Hour: 4:00am Day: 22 Month: November Year: 1985

Plugging proposal received from Tony Ernst

(company name) Wheatstate Oilfield Service (phone) 316-672-7514

Work: Keep hole full of heavy mud + spot cement plugs + through
 drill pipe. 1st plug @ base of anhydrite w/50sx cement. 2nd
 plug @ 1150' w/70sx cement. 3rd plug @ 30' below base of
 surface pipe w/50sx cement. 4th plug @ 40' w/solid Bridge
 plug + 10sx cement. Circulate Rathole w/10sx cement
 Circulate Mousehole w/10sx cement
 Plugging Proposal Received by Richard W. Lacey
 (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:00am Day: 22 Month: November Year: 1985

ACTUAL PLUGGING REPORT Kept hole full of heavy mud + spotted cement
 plugs through drill pipe. 1st plug @ 2155' w/50sx cement
 2nd plug @ 1150' w/70sx cement. 3rd plug @ 40'
 w/solid Bridge Plug + 10sx Circulated Rathole + Mousehole
 w/10sx each

Anhydrite @ 2140' Elevation 2711

Remarks: Allied pumped 60/40 pozmix 6% gel cement
 (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-6-85

INV. NO. 11280

DEC 2 1985
 12-02-1985
 CONSERVATION DIVISION
 WICHITA, KANSAS

Signed Richard W. Lacey
 (TECHNICIAN)