

To: 1 070380  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

7-29-87  
API NUMBER 15-101-21,375-00-00  
SW NE SW, SEC. 8, T 16 S, R 29 W/E  
1650 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Jennison Well # 1

Operator: Viking Resources  
Name & Address 120 South Market, Suite 518  
Wichita, KS 67202-3819

County Lane 145.11  
Well Total Depth 4465 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 213

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mallard Drilling Company License Number 4958

Address Box 1009, McPherson, KS 67460

Company to plug at: Hour: 6:35 a.m. Day: 29 Month: 7 Year: 19 87

Plugging proposal received from Arnie Hess

(company name) Mallard Drilling Company (phone) 913-731-2869

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2714'  
Anhydrite 2122-53'

1st plug at base anhydrite with 50 sx cement, 2nd plug at 1400' with 80 sx cement,  
3rd plug at 240' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:50 a.m. Day: 29 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2149' with 50 sx cement,

2nd plug at 1400' with 80 sx cement,  
3rd plug at 240' with 40 sx cement,  
4th plug at 40-0' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

08-03-1987

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED (do not) observe this plugging.

Signed Dan Jordan (TECHNICIAN)

DATE 8-5-87

INV. NO. 17707

7-29

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 4-30-87 month day year

API Number 15-101-21,375-00-00 East SW. NE SW Sec. 8 Twp. 16 S, Rg. 29 X West 1650 Ft. from South Line of Section 3630 Ft. from East Line of Section

OPERATOR: License # 5011 Name Viking Resources Address 120 S. Market, Suite 518 City/State/Zip Wichita, KS 67202-3819 Contact Person Jim Deylin Phone (316) 262-2502

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 990 feet County Lane Lease Name Denison Well # 1 Ground surface elevation Unknown feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water 60 Depth to bottom of usable water 1325 Surface pipe by Alternate: 1 2 X Surface pipe planned to be set 200 Conductor pipe required None Projected Total Depth 4500 feet Formation Mississippian

CONTRACTOR: License # Unknown Name Mallard City/State Well Drilled For: X Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl X Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 31 March 1987 Signature of Operator or Agent Arnie B. Deylin Title Operator

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. This Authorization Expires 10-2-87 Approved By 4-1-87

Move 7-18-87 set 200' 7-29-87 still Drilling

Handwritten initials and notes: P.H.K. No

SW. NE SW Sec. 8 Twp. 16 S, Rg. 29 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth, feet depth with, and size of plug. Includes entries for 1st plug @ Base of Anhydrite, 2nd plug @ 1375, 3rd plug @ 30' below base of surf, 4th plug @ 0-40, 5th plug @ , and (2) Rathole with 15.

Arnie Hess

Vertical log entries: PUSHER, TD 4465 FORMATION Mead, SURFACE PIPE 8 7/8" 213', ANHYDRITE 2122'-53' ELEVATION 2714', STARTING TIME & DATE 7-29-87 6:35 AM, COMPLETION TIME & DATE 9:50 AM, 1st PLUG @ 2144 FT. W/ 50 SX, 2nd PLUG @ 1400 FT. W/ 80 SX, 3rd PLUG @ 240 FT. W/ 40 SX, 4th PLUG @ 40-0 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15, MOUSE HOLE CIRCULATED W/ 0, WATER WELL PLUGGED W/ bentonite NONE, CEMENT COMPANY Allied, TECHNICIAN 6/4 6% gel Dan Goodrow Saw none

STATE OF KANSAS DEPARTMENT OF REVENUE AUG 3 1987 08-03-1987 WICHITA, KANSAS