

1050286

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,002-00-00

NW SW SW, SEC. 13, T 16 S, R 29  
990 FSL feet from ~~N~~ SE Corner of section line  
4950 FCL feet from ~~W~~ SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Sam Well # 1-13

Operator: Gear Petroleum Co., Inc.

County Lane

Name & Address 300 Sutton Place

Well Total Depth 4570 148.53 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Co. License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: noon Day: 17 Month: July Year: 19 84

Plugging proposal received from Harold Dinkel

(company name) Warrior (phone) 913-726-4875

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2130' with 50 sx cement

2nd plug at 1000' with 40 sx cement

3rd plug at 380' with 40 sx cement solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement. Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

7th plug to circulate mouse hole with 10 sx cement

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 1:45 pm Day: 17 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2130' with 50 sx cement, 2nd plug at 1000' with 40 sx

cement, 3rd plug at 380' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx cement

7th plug to circulate mouse hole with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION 07-24-1984 JUL 24 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc

(if additional description is necessary, use BACK of this CONSERVATION DIVISION Wichita, Kansas

INVOICED

DATE 7-30-84

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 2727

7 17 AUG 16 1984