

1060220

TO: STATE CORPORATION COMMISSION

API NUMBER 15-101-20,854-00-00  
NE SW SW SEC. 31, T 16 S, R 29 W

CONSERVATION DIVISION - PLUGGING SECTION 900 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4180 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME JENNISON B WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY LANE

OPERATOR LICENSE # 8914 WELL TOTAL DEPTH 4590 FEET

OPERATOR: H & C OIL OPERATING, INC. PRODUCTION CSG: SIZE 5 1/2" @ 4589' WITH 175 SX

NAME AND PO BOX 86 SURFACE CASING: SIZE 8 5/8" @ 420' WITH 225 SX

ADDRESS PLAINVILLE, KS 67663

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D/A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 31 RUSSELL, KS 67665-0031

COMPANY TO PLUG AT: HOUR: 10:10 AM DAY: 30 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM \_\_\_\_\_

(COMPANY NAME) ALLIED CEMENTING (PHONE) 785-483-2627

WERE: PERFS AT 4542-54, 4615-18, 4489-91, 4469-72, 4184-90, 4164-68  
LOG & REPORTS SHOW CEMENT FROM 2200' TO SURFACE.

09-18-2000

BOTTOM PLUG PUMP 40 SX CEMENT WITH 300# HULLS. PUMP 20 SX GEL THEN 165 SX CEMENT.

PRESSURE TO 600#. SHUT IN WITH 400#. PUMP 5 SX CEMENT DOWN BACKSIDE AND PRESSURE TO 500# AND HELD.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 30 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT \_\_\_\_\_

BOTTOM PLUG PUMP 40 SX CEMENT WITH 300# HULLS. PUMP 20 SX GEL THEN 165 SX CEMENT.

PRESSURED TO 600#, SHUT IN WITH 400#. PUMPED 5 SX CEMENT DOWN BACKSIDE AND PRESSURED TO 500# AND HELD.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Michael J. Maier  
(TECHNICIAN) FORM CP-2/3

*(Handwritten initials and signature)*